

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUBMIT IN DUPLICATE*
(Other information on reverse side)

5. Lease Designation and Serial No.

State U-01194

6. If Indian, Allottee or Tribe Name

Not Applicable

7. Unit Agreement Name

Natural Buttes

8. Farm or Lease Name

NBU

9. Well No.

132

10. Field and Pool, or Wildcat

Natural Buttes 630

11. Sec., T., R., M., or Blk. and Survey or Area

Sec. 26, T9S, R21E

12. County or Parrish 13. State

Uintah Utah

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work

DRILL

DEEPEN

PLUG BACK

b. Type of Well

Oil Well

Gas Well

Other

Single Zone

Multiple Zone

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address of Operator

P.O. Box 749, Denver, Colorado 80201-0749

4. Location of Well (Report location clearly and in accordance with any State requirements.)*

At surface

594' FNL 850' FWL (NW1/4NW1/4)

26-95-21E

At proposed prod. zone

Same

14. Distance in miles and direction from nearest town or post office*

Approximately 10 Miles Southeast of Ouray, Utah

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drlg. line, if any)

594'

16. No. of acres in lease

1082.97

17. No. of acres assigned to this well

80

18. Distance from proposed location* to nearest well, drilling, completed, or applied for, on this lease, ft.

1500'

19. Proposed depth

8100' DSTC

20. Rotary or cable tools

Rotary

21. Elevations (Show whether DF, RT, GR, etc.)

4965' GR

22. Approx. date work will start*

January 30, 1991

23. PROPOSED CASING AND CEMENTING PROGRAM

Size of Hole	Size of Casing	Weight per Foot	Setting Depth	Quantity of Cement
12-1/4"	8-5/8" J-55	24.0#	0-250'	Circulate to Surface
7-7/8"	5-1/2" K-55	17.0#	0-T.D.	1000-sx Lite + Class "G"

TECHNICAL REVIEW

Engr. SM 1-16-91

Geol. DL 1/14/91

Surface BL 1/11/91

RECEIVED

JAN 04 1991

DIVISION OF
OIL, GAS & MINING

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. Dale Heitzman
Signed: Dale Heitzman

Title: Authorized Agent

Date: 1-2-91

(This space for Federal or State office use)

API Permit No. 43-047-31938

Approval Date

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

Approved by
Conditions of approval, if any:

Title


DATE: 1-16-91
BY: [Signature]

*See Instructions On Reverse Side WELL SPACING: 615-2-3

T9S, R21E, S.L.B.&M.

COASTAL OIL & GAS CORP.

Well Location, COG NBU #132, located as shown in the NW 1/4 NW 1/4 of Section 26, T9S, R21E, S.L.B.&M. Uintah County, Utah




BASIS OF ELEVATION

BENCH MARK IN THE NW 1/4 OF SECTION 26, T9S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4934 FEET.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



UINTAH ENGINEERING & LAND SURVEYING
 P. O. BOX 1758 - 85 SOUTH - 200 EAST
 VERNAL, UTAH - 84078

SCALE 1" = 1000'	DATE 12-26-90
PARTY L.D.T. J.T.K. R.E.H.	REFERENCES G.L.O. PLAT
WEATHER COLD	FILE COASTAL OIL & GAS CORP.

▲ = SECTION CORNERS LOCATED.

COASTAL OIL & GAS CORPORATION
NBU #132
NW~~1~~NW~~1~~, Section 26, T9S, R21E
Uintah, Utah

Drilling Prognosis

1. Estimated Formation Tops:

Surface	Uinta
Green River	1270'
Wasatch - Mesa Verde	4500' - 8000'
Total Depth	8100'

2. Pressure Control Equipment:

Type : One 10" X 3000 psi annular preventer.
One 10" X 3000 psi double ram preventer (blind ram above, pipe ram below).
One wing with two manual valves and one choke.
One positive choke and one adjustable.

Testing Procedure : The BOP and choke manifold will be pressure tested to the rated working pressure of 70% of the internal yield strength of the surface casing, whichever is less, for a period of 15 minutes upon installation; once every thirty days and/or when flange seals are broken if a "nipple-up" or "nipple-down" takes place.

3. Drilling Fluids Program:

<u>Interval</u>	<u>Type</u>	<u>Weight</u>	<u>Viscosity</u>	<u>Fluid Loss</u>
0-250'	Aerated Water	--	--	--
250-8100'		--	--	--

Drilling mud inventory will be stockpiled on the location and will not be less than the total amount needed for the mud system as required to drill this well.

4. Evaluation Program:

Logs : DIL with Caliper - Surface to Total Depth
FDC-CNL - Approximately 1500' to Total Depth


DST's : None Anticipated

Cores : None Anticipated

5. Abnormal Conditions:

No abnormal temperatures or pressures are anticipated. No H₂S gas has been reported or known to exist from previous drilling in the area at this depth. Maximum anticipated bottom hole pressure equals 2000 pounds.

3,000 psi Working Pressure BOP



Test Procedure

- 1) Flush BOP's and all lines to be tested with water.
- 2) Run test plug on test joint and seat in casing head (leave valve below test plug open to check for leak).
- 3) Test the following to rated pressure:
 - a) inside blowout preventer
 - b) lower kelly cock
 - c) upper kelly cock
 - d) stand pipe valve
 - e) lines to mud pump
 - f) kill line to BOP's
- 4) Close and test pipe rams to rated pressure.
- 5) Close and test Hydril to rated pressure.
- 6) Back off and leave test plug in place. Close and test blind rams to rated pressure.
- 7) Test all choke manifold valves to rated pressure.
- 8) Test kill line valves to rated pressure.

COASTAL OIL AND GAS
NBU #132

NWNW Sec. 26, T9S, R21E

Uintah County, Utah

Supplement to Application for Permit to Drill

1. Location and Type of Water Supply:

- A. Water for drilling will be obtained from an existing industrial water well (Uintah #1) owned by Target Trucking, Inc. and located in the SE $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$ Section 16, Township 10 South, Range 21 East, Uintah County, Utah; Permit Number 49-991 (A57530).

2. Methods of Handling Waste Disposal:

- A. Sewage - self-contained, chemical toilets will be provided for human waste disposal. Upon completion of operations, the holding tanks will be pumped and the contents disposed of in a municipal sewage treatment facility or other authorized disposal facility.
- B. Garbage and other waste materials - all trash will be contained in a portable trash cage. Upon completion of operations, all trash will be hauled to an approved sanitary landfill.
- C. Cuttings and drilling fluids - the cuttings will be deposited in the reserve pit. Drilling fluids will be contained in reserve pit and allowed to evaporate. The reserve pit will be designed to prevent the collection of surface runoff and will be constructed with a minimum of one-half (1/2) the total depth below the original ground surface on the lowest point within the pit. The reserve pit will not be lined unless fractured rock or extremely porous soil/rock formations are encountered.

3. Plans for Reclamation of the Surface:

- A. Backfilling, leveling and re-contouring are planned as soon as the reserve pit dries. Waste and spoil materials will be disposed of immediately upon completion of drilling and workover activities. If production is established, the unneeded areas of the location will be reclaimed as soon as the reserve pit dries.
- B. Upon completion of backfilling, leveling and re-contouring, the stockpiled topsoil will be evenly spread over the reclaimed area(s). All disturbed surfaces (including access road and well pad areas) will be reseeded using the seed mixture recommended by the State of Utah. Seed will be drilled on the contour to an approximate depth of 1/2 inch.
- C. Three sides of the reserve pit will be fenced during drilling operations. Prior to rig release, the reserve pit will be fenced on the fourth side to prevent livestock and wildlife from becoming entrapped, and the fencing will be maintained until leveling and cleanup are accomplished.

3. Plans for Reclamation of the Surface: Continued

- D. If any oil is on the pits and is not immediately removed after operations cease, the pit containing the oil or other adverse substances will be flagged overhead or covered with wire mesh.
- E. The reclamation operations will begin after the drilling rig is removed. Removal of oil or other adverse substances will begin immediately or area will be flagged and fenced. Other cleanup will be done as needed. Rehabilitation operations should be completed by the Fall of 1991.

4. Other Information:

- A. A cultural resource inventory of the proposed well site and access road has been completed.


5. Surface Ownership:

State of Utah
Division of State Lands and Forestry
Salt Lake City, Utah
Telephone: (801) 538-5508

6. Contact for Additional Data if Required:

Heitzman Drill-Site Services
Dale Heitzman/Bob Anderson
P. O. Box 3579
Casper, Wyoming 82602
Telephone: (307) 266-4840


COASTAL OIL & GAS CORP.
 LOCATION LAYOUT FOR
 COG NBU #132
 SECTION 26, T9S, R21E, S.L.B.&M.



APPROXIMATE YARDAGES


CUT		EXCESS MATERIAL AFTER	
(6") Topsoil Stripping	= 1,070 Cu. Yds.	5% COMPACTION	= 2,300 Cu. Yds.
Pit Volume (Below Grade)	= 2,440 Cu. Yds.	Topsoil & Pit Backfill	= 2,290 Cu. Yds.
Remaining Location	= 2,830 Cu. Yds.	(1/2 Pit Vol.)	
TOTAL CUT	= 6,340 CU.YDS.	EXCESS UNBALANCE	= 10 Cu. Yds.
FILL	= 3,840 CU.YDS.	(After Rehabilitation)	

EXCESS MATERIAL AFTER	
5% COMPACTION	= 2,300 Cu. Yds.
Topsoil & Pit Backfill	= 2,290 Cu. Yds.
(1/2 Pit Vol.)	
EXCESS UNBALANCE	= 10 Cu. Yds.
(After Rehabilitation)	




SCALE: 1" = 50'
 DATE: 12-26-90
 Drawn By: T.D.H.

TYP. LOCATION LAYOUT



NOTES:
 Elev. Ungraded Ground At Loc. Stake = 4965.1'
 FINISHED GRADE ELEV. AT LOC. STAKE = 4963.0'

FIGURE #1



TOPOGRAPHIC
MAP "A"

DATE 12-3-90



COASTAL OIL & GAS CORP.

COG NBU #132

SECTION 26, T9S, R21E, S.L.B.&M.

DRILLING LOCATION ASSESSMENT

**State of Utah
Division of Oil, Gas and Mining**

OPERATOR: COASTAL OIL & GAS WELL NAME: NBU #132
SECTION: 26 TWP: 9S RNG: 21E LOC: 594 FNL 850 FWL
QTR/QTR NW/NW COUNTY: UINTAH FIELD: NATURAL BUTTES
SURFACE OWNER: STATE OF UTAH
SPACING: NATURAL BUTTES UNIT
INSPECTOR: Brad Hill DATE AND TIME: 12/27/90 9:00

PARTICIPANTS: Gil Hunt-DOGMA, Jim Forman-Coastal, Dale Heitzman-Permit Agent, Robert Kay-Uintah Engineering, Harley Jackson-Jackson Construction.

REGIONAL SETTING/TOPOGRAPHY: The proposed location is in the southeastern Uinta Basin in a topographic area of small rolling hills which are dissected by shallow intermittent drainages.

LAND USE:

CURRENT SURFACE USE: None

PROPOSED SURFACE DISTURBANCE: A roughly rectangular pad will be constructed with approximate dimensions of 325'X 160' with a 125'X 75' extension for the reserve pit. (see application) An access road 500 feet long will also be constructed.

AFFECTED FLOODPLAINS AND/OR WETLANDS:None

FLORA/FAUNA: Rabbitbrush, Sage, Curley grass, Snakeweed, Saltbush/Deer, Antelope, Coyote, Rabbits

ENVIRONMENTAL PARAMETERS

SURFACE GEOLOGY

SOIL TYPE AND CHARACTERISTICS: Silty-sand with abundant sandstone fragments and cobbles.

SURFACE FORMATION & CHARACTERISTICS: Uinta Formation consisting of interbedded sandstones and shales.

EROSION/SEDIMENTATION/STABILITY: No active erosion or sedimentation at present. Location should be stable.

PALEONTOLOGICAL POTENTIAL: None observed.

SUBSURFACE GEOLOGY

OBJECTIVES/DEPTHS: Green River-1270', Wasatch-4500', Mesa Verde-8000'

ABNORMAL PRESSURES-HIGH AND LOW: None anticipated

CULTURAL RESOURCES/ARCHAEOLOGY: Cleared by Metcaff and Associates.

CONSTRUCTION MATERIALS: Onsite materials will be used for construction.

SITE RECLAMATION: The area will be recontoured and reseeded as per State Lands instructions.

RESERVE PIT

CHARACTERISTICS: The reserve pit will be rectangular with dimensions of 125'X 75'X 10'.

LINING: None needed.

MUD PROGRAM: The entire well will be drilled with aerated water.

DRILLING WATER SUPPLY: To be purchased from Target trucking.

STIPULATIONS FOR APD APPROVAL

None needed. ~~from running off of the location.~~

ATTACHMENTS

Photographs will be placed on file.

OPERATOR Coastal Oil Gas Corp. No. 130 DATE 1-9-91

WELL NAME NBU 130

SEC N44W 01W T 9S R 01E COUNTY Montah

43-047-31938
API NUMBER

State (3)
TYPE OF LEASE

CHECK OFF:

PLAT.

BOND

NEAREST WELL

LEASE

FIELD SLBM

POTASH OR OIL SHALE

PROCESSING COMMENTS:

1991 P.O.D. approved 10-20-90 per Dennis Thompson -
water permit 49-991 (A57530) target ducking
Permit 1-9-91 / Geology when 1-11-91
Oil shale area

APPROVAL LETTER:

SPACING:

R615-2-3

Natural Buttes
UNIT

R515-3-2

N/A
CAUSE NO. & DATE

R615-3-3

STIPULATIONS:

Oil shale stipulation
cc: State Lands



State of Utah

DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

Norman H. Bangarter
Governor

Dee C. Hansen
Executive Director

Dianne R. Nielson, Ph.D.
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

January 16, 1991

Coastal Oil & Gas Corporation
P. O. Box 749
Denver, Colorado 80201-0749

Gentlemen:

Re: NBU 132 - NW NW Sec. 26, T. 9S, R. 21E - Uintah County, Utah
594' FNL, 850' FWL

Approval to drill the referenced well is hereby granted in accordance with Section 40-6-18, Utah Code Annotated, as amended 1983; and predicated on R615-2-3, Oil and Gas Conservation General Rules, subject to the following stipulation:

1. Special attention is directed to compliance with R615-3-31, Oil and Gas Conservation Rules, which prescribes drilling procedures for designated oil shale areas.

In addition, the following actions are necessary to fully comply with this approval:

1. Spudding notification within 24 hours after drilling operations commence.
2. Submittal of an Entity Action Form within five working days following spudding and whenever a change in operations or interests necessitates an entity status change.
3. Submittal of the Report of Water Encountered During Drilling, Form 7.
4. Prompt notification if it is necessary to plug and abandon the well. Notify R. J. Firth, Associate Director, (Office) (801) 538-5340, (Home) 571-6068, or Jim Thompson, Lead Inspector, (Home) 298-9318.
5. Compliance with the requirements of R615-3-20, Gas Flaring or Venting, Oil and Gas Conservation General Rules.

Page 2
Coastal Oil & Gas Corporation
NBU 132
January 16, 1991

6. Prior to commencement of the proposed drilling operations, plans for facilities for disposal of sanitary wastes at the drill site shall be submitted to the local health department. These drilling operations and any subsequent well operations must be conducted in accordance with applicable state and local health department regulations. A list of local health departments and copies of applicable regulations are available from the Division of Environmental Health, Bureau of General Sanitation, telephone (801) 538-6121.
7. This approval shall expire one (1) year after date of issuance unless substantial and continuous operation is underway or an application for an extension is made prior to the approval expiration date.

The API number assigned to this well is 43-047-31938.

Sincerely,



R. J. Firth
Associate Director, Oil & Gas

tas
Enclosures
cc: Bureau of Land Management
Division of State Lands
J. L. Thompson
we14/1-6

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

5. Lease Designation and Serial No.

State U-01194

6. If Indian, Allottee or Tribe Name

Not Applicable

7. Unit Agreement Name

Natural Buttes

8. Farm or Lease Name

NBU

9. Well No.

132

10. Right and Pool, or Wildcat

Natural Buttes

11. Sec., T., R., M., or Bk. and Survey or Area

Sec. 26, T9S, R21E

12. County or Parish 13. State

Uintah Utah

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work

DRILL

DEEPEN

PLUG BACK

b. Type of Well

Oil Well

Gas Well

Other

Single Zone

Multiple Zone

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address of Operator

P.O. Box 749, Denver, Colorado 80201-0749

JAN 23 1991

4. Location of Well (Report location clearly and in accordance with any State requirements.)*

At surface

594' FNL 850' FWL (NW $\frac{1}{2}$ NW $\frac{1}{2}$)

26-95-21E

At proposed prod. zone

Same

43-047-31928 DR

14. Distance in miles and direction from nearest town or post office*

Approximately 10 Miles Southeast of Ouray, Utah

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. line, if any)

594'

16. No. of acres in lease

1082.97

17. No. of acres assigned to this well

80

18. Distance from proposed location* to nearest well, drilling, completed, or applied for, on this lease, ft.

1500'

19. Proposed depth

8100'

20. Rotary or cable tools

Rotary

21. Elevations (Show whether DF, RT, GR, etc.)

4965' GR

22. Approx. date work will start*

January 30, 1991

23. PROPOSED CASING AND CEMENTING PROGRAM

Size of Hole	Size of Casing	Weight per Foot	Setting Depth	Quantity of Cement
12-1/4"	8-5/8" J-55	24.0#	0-250'	Circulate to Surface
7-7/8"	5-1/2" K-55	17.0#	0-T.D.	1000 ex Lite + Class "G"

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

Signed

Dale Heitzman

Title

Authorized Agent

Date

1-2-91

(This space for Federal or State office use)

Permit No.

ACCEPTED BY DEW FOR UNIT PURPOSES ONLY

Approval Date

Approved by

Title

Date JAN 18 1991

Conditions of approval, if any:

UTOBO-1M32

WATER PERMIT OK

DIVISION OF OIL, GAS AND MINING

API NO. 43-047-31938 *del*

SPUDDING INFORMATION

NAME OF COMPANY: COASTAL OIL & GAS CORPORATION

WELL NAME: NBU 132

SECTION NWNW 26 TOWNSHIP 9S RANGE 21E COUNTY UINTAH

DRILLING CONTRACTOR LEON ROSS

RIG # _____

SPUDDED: DATE 4-1-91

TIME 11:00

HOW DRY

DRILLING WILL COMMENCE 4-15-91 - COASTAL #2

REPORTED BY CAK

TELEPHONE # _____

DATE 4-1-91 SIGNED _____ TAS TAKEN BY: JLT

DIVISION OF OIL, GAS AND MINING

WATER PERMIT OK

API NO. 43-047-31938 *del*

SPUDDING INFORMATION

NAME OF COMPANY: COASTAL OIL & GAS CORPORATION

WELL NAME: NBU #132

SECTION SWNE 26 TOWNSHIP 9S RANGE 21E COUNTY UINTAH

DRILLING CONTRACTOR COASTAL

RIG # 2

SPUDDED: DATE 4-1-91

TIME 11:00

HOW DRY

DRILLING WILL COMMENCE 4-22-91

REPORTED BY Carol K.

TELEPHONE # _____

DATE 4-20-91 SIGNED TAS

STATE OF UTAH
DIVISION OF OIL, GAS & MINING
CEMENTING OPERATIONS

MICROFICHE

COMPANY NAME: COASTAL OIL & GAS COMPANY MAN: DON NICHOLS
WELL NAME: NBU #132 WELL SIGN: NO 43-047-31938
QTR QTR: NWNW SECTION: 26 TWP: 09 SOUTH RANGE: 21 EAST
CEMENTING COMPANY: HALLIBURTON SERVICES
INSPECTOR: CAROL KUBLY DATE: 04/22/91

CEMENTING OPERATIONS:

PLUGBACK: _____ SQUEEZE: _____ CASING: _____ P-A ZONE: _____
SURFACE CASING: YES INTERMEDIATE: _____ PROD. CASING: _____
PERFORATIONS: _____ SQUEEZE PRESSURE: _____

CASING INFORMATION:

SIZE: 8 5/8" GRADE: J-55 WEIGHT: 24 # LENGTH: 250'
HOLE SIZE: 12 1/4" DEPTH: 260'

SLURRY INFORMATION

- CLASS:
LEAD: PREMIUM + AG + 2% CACL + 1/4 #/SK FLOCELE
- SLURRY WEIGHT:
LEAD: 15.6 TAIL:
- WATER (GAL / SX)
LEAD: 5.20 TAIL:
- COMPRESSIVE STRENGTH
PSI AT: 1675 HOUR: 12 HOURS

PIPE CENTRALIZED: X3 + 1 FAST GRIP CEMENTING STAGES: ONE
LOST RETURNS: NO REGAIN RETURNS: NO BARRELS LOST: 0
TOP OF CEMENT: SFC CEMENT TO SURFACE?: YES % EXCESS: 100 %

ADDITIONAL COMMENTS: PUMPED 46 BBLs FRESH WATER THEN 20 BBL GEL WATER
THEN 180 SXS (37.8 BBL) CMT SLURRY THEN DROPPED PLUG THEN DISPLACED WITH
14.5 BBL FRESH WATER. LEFT 30' OF CEMENT IN CASING BELOW PLUG PLUS 1.5
BBL CMT ABOVE PLUG. HYDROSTATIC PRESSURE ON CEMENT HEAD = 100 #

OPERATOR Coastal Oil & Gas Corporation
ADDRESS P.O. Box 749, Denver, CO 80201-0749

OPERATOR ACCT. NO. M0230

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	2900		43-047-31950 ^{del}	NBU #133	SWNE	28	9S	21E	Uintah	4/9/91	4/9/91
WELL 1 COMMENTS: Federal-Lease Field-Natural Buttes Units-Natural Buttes Proposed Zone-wstrc (Entity added 4-19-91) <i>for</i> * Both wells.											
B	2900		43-047-31938 ^{del}	NBU #132	NWNW	26	9S	21E	Uintah	4/1/91	4/1/91
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

RECEIVED

APR 17 1991

DIVISION OF
OIL GAS & MINING

Eileen Danni Dey
Signature Eileen Danni Dey

Regulatory Analyst 4/15/91
Title Date

Phone No. (303) 573-4476

- ACTION CODES (See instructions on back of form)
- A - Establish new entity for new well (single well only)
 - B - Add new well to existing entity (group or unit well)
 - C - Re-assign well from one existing entity to another existing entity
 - D - Re-assign well from one existing entity to a new entity
 - E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Lease Designation and Serial Number	State U-01194
7. Indian Allottee or Tribe Name	N/A
8. Unit or Communitization Agreement	Natural Buttes Unit
9. Well Name and Number	NBU #132
10. API Well Number	43-047-31938
11. Field and Pool, or Wildcat	Natural Buttes

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells; deepen existing wells; or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT— for such proposals.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)	
2. Name of Operator Coastal Oil & Gas Corporation	
3. Address of Operator P. O. Box 749, Denver, Colorado 80201-0749	
4. Telephone Number (303) 573-4476	County : Uintah State : UTAH
5. Location of Well Footage : 594' FNL & 850' FWL QQ. Sec. T. R. M. : NWNW Section 26, T9S-R21E	

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

- Abandonment
- Casing Repair
- Change of Plans
- Conversion to Injection
- Fracture Treat
- Multiple Completion
- Other
- New Construction
- Pull or Alter Casing
- Recompletion
- Shoot or Acidize
- Vent or Flare
- Water Shut-Off

Approximate Date Work Will Start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- Abandonment
- Casing Repair
- Change of Plans
- Conversion to Injection
- Fracture Treat
- Other Report of spud
- New Construction
- Pull or Alter Casing
- Shoot or Acidize
- Vent or Flare
- Water Shut-Off

Date of Work Completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.
• Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

MIRU Leon Ross Drilling, Inc. Spud surface hole @ 11:00 A.M., 4/1/91. Drilled 12-1/4" hole to 260'. Ran 6 jts. 8-5/8" 24#, K55, ST&C and set @ 258'. Cmt'd. w/180 sx. Cl "G" cmt. + additives. PD @ 12:04 P.M., 4/2/91.

RECEIVED

MAY 13 1991

DIVISION OF
OIL GAS & MINING

I hereby certify that the foregoing is true and correct

Name & Signature

Colleen Dawn Deay
Colleen Dawn Deay

Title Regulatory Analyst Date 5/8/91

State Use Only)

Coastal Oil & Gas
NBU #132 43-047-31938
Section 26
Township 9S
Range 21E
Operator-Coastal Oil & Gas
Contractor-Coastal Drilling #1
5-31-91
Tested by Paul Yoder

RECEIVED

JUN 20 1991

DIVISION OF
OIL GAS & MINING

QUICK TEST INC.
OFFICE (801) 789-8159

Coastal Oil & Gas
NBU #132
5-31-91

TEST #	ITEM TESTED	PRESSURE	MIN. HELD	RESULTS
1	1st set choke manifold valves	2000	10	No visible leaks
2	2nd set choke manifold valves	2000	10	No visible leaks
3	Safety valve	2000	10	No visible leaks
4	Upper kelly cock	2000	10	No visible leaks
5	Lower kelly cock	2000	10	No visible leaks
6	Piperams, 1st choke, 1st kill	2000	10	No visible leaks
7	Hydril, 1st choke, 1st kill	1500	10	No visible leaks
8	Blindrams, 2nd set choke manifold valves	2000	10	No visible leaks
9	Casing	1500	30	No visible leaks

RECEIVED


JUN 20 1991

DIVISION OF
OIL GAS & MINING

PRINTED IN U.S.A. ©

DAY

NIGHT



CALIBRATED
CHARTS

Capital Oil & Gas

METER NUMBER: _____
 DATE PUT ON: _____
 DATE TAKEN OFF: _____

NO. _____
 BR-2373
 B 0-10.8
 231



NO. _____
 A1

TOBE TAKEN OFF: _____
 DATE TAKEN OFF: _____

RECEIVED

JUN 20 1991

DIVISION OF
OIL GAS & MINING



RECEIVED

JUN 20 1991

DIVISION OF
OIL GAS & MINING

COASTAL OIL & GAS CORP.
CASTALDRIL #1
5-31-91
NBU 132

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Lease Designation and Serial Number	State U-01194
7. Indian Allottee or Tribe Name	N/A
8. Unit or Communitization Agreement	Natural Buttes Unit
9. Well Name and Number	NBU #132
10. API Well Number	43-047-31938
11. Field and Pool, or Wildcat	Natural Buttes

SUNDRY NOTICES AND REPORTS

Do not use this form for proposals to drill new wells, deepen existing wells, or to re-enter plugged and abandoned wells.
Use APPLICATION FOR PERMIT for such proposals.

JUN 28 1991

1. Type of Well
 Oil Well Gas Well Other (specify) _____

2. Name of Operator
 Coastal Oil & Gas Corporation

3. Address of Operator
 P. O. Box 749, Denver, Colorado 80201-0749

5. Location of Well
 Footage : 594' FNL & 850' FWL
 Q. Sec. T. R. M. : NWNW Section 26, T9S-R21E

4. Telephone Number
 (303) 573-4476

County : Uintah
 State : UTAH

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

- Abandonment
- Casing Repair
- Change of Plans
- Conversion to Injection
- Fracture Treat
- Multiple Completion
- Other _____
- New Construction
- Pull or Alter Casing
- Recompletion
- Shoot or Acidize
- Vent or Flare
- Water Shut-Off

Approximate Date Work Will Start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- Abandonment
- Casing Repair
- Change of Plans
- Conversion to Injection
- Fracture Treat
- Other Report of Operations
- New Construction
- Pull or Alter Casing
- Shoot or Acidize
- Vent or Flare
- Water Shut-Off

Date of Work Completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.
* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please see the attached chronological report for the drilling operations on the above-referenced well.

14. I hereby certify that the foregoing is true and correct

Name & Signature

Robert David Day

Title

Regulatory Analyst

Date

6/26/91

(State Use Only)

COASTAL OIL & GAS CORPORATION
CHRONOLOGICAL HISTORY

NBU #132
NATURAL BUTTES UNIT
UINTAH COUNTY, UTAH
COASTALDRIL #1
WI: 100% COGC AFE: 13014
ATD: 6200' (WASATCH) SD: 5/31/91
CSG: 8-5/8" @ 270'
DHC(M\$): 158.9

NW/NW SECTION 26-T9S-R21E

- 4/3/91 260' MIRU Leon ross. Spud @ 11:00 a.m., 4/1/91. Drill 12-1/4" hole to 260'. run 6 jts 8-5/8" 24# K-55 ST&C (256.94') & set @ 258'. Equipped w/guide shoe and 3 centralizers. Cmt w/180 sx prem "G" w/2% CaCl₂ & 1/4#/sx Flocele. Wt 15.6#/gal, Yd 1.18 cu ft/sx. Drop plug and displ w/14.5 BFW. SD 12:04 p.m., 4/2/91. Good returns, circ 6 bbls cmt to pit. Drill rat & mouse hole. CC: \$23,126.
- 6/1/91 900' Drlg 630'/7-1/2 hrs. Spud @ 10:00 p.m., 5/31/91. NU BOP's, test to 2000 psi, hydril and csg to 1500 psi, OK. PU BHA, drill cmt plug & shoe, tag cmt @ 240'. Drlg, svy: 1-1/4 deg @ 795'. Drlg w/mist. pH 12.0, air 1400 SCFM. CC: \$60,623.
- 6/2/91 2675' Drlg 1775'/22.5 hrs. Drlg, svys: 1 deg @ 1301'; 1-1/4 deg @ 2309'. Start aerated @ 1824', water @ 1755'. Drlg w/aerated wtr, pH 11.0, 700 CFM. CC: \$69,701.
- 6/3/91 3640' Drlg 965'/18.5 hrs. Drlg, svy: 1-3/4 deg @ 3132'. TFNB, work BOP's. Wash & ream 70' to btm, no fill. Drlg w/aerated wtr. pH 10.5, 700 CFM. CC: \$80,577.
- 6/4/91 4600' Drlg 960'/23 hrs. Drlg, RS, chk BOP. Drlg, svy: 1-3/4 deg @ 4203'. Drlg w/wtr. MW 8.4, VIS 27, WL N/C, PH 10.5. CC: \$89,017.
- 6/5/91 5340' Drlg 740'/23 hrs. Drlg, RS, check BOP. Drlg w/aerated wtr. Svy: 3-3/4 deg @ 5245'. MW 8.4, VIS 27, WL 10.5, 700 SCFM & 40 SPM. CC: \$97,621.
- 6/6/91 5936' Drlg 596'/23 hrs. Drlg, RS, check BOP. Svy: 3 deg @ 5560'. Drlg w/aerated wtr. MW 8.4, VIS 27, WL N/C, PH 10.5, 600 SCFM. CC: \$103,731.
- 6/7/91 6377' RU Howco (HLS) to run E logs. 441'/16-1/2 hrs. Drlg, RS, check BOP. Drlg, circ & cond hole. Short trip 15 stds - OK. Displace hole w/500 bbls 10 ppg brine. Drop svy, TOOH, SLM. Strap 6375.30', no correction. RU HLS. Run DIL-GR Caliper-CNL-FDC. Drlg brks from 5734-5747'; 5879-5902'; 6182-6193'; 6285-6307'; 6324-6331'. Drlg w/aerated wtr. Svy: 2-3/4 deg @ 6352'. MW 8.4, VIS 27, WL N/C, PH 11.0, 600 SCFM. CC: \$112,418.
- 6/8/91 6377' RDRT Logging w/HLS. Ran DIL-GR-Cal-FDC-GR to surface; CNL-FDC to 2700'; logger's TD 6380'. BHT 153°F. TIH, RU csg crew, LD DP. Run 155 jts (6383.09') 5-1/2" 17# J-55 LT&C. FS @ 6376'; FC @ 6333', 10 centralizers. RU Howco, wash to 6362', bridge @ 6362'. Cmt w/210 sx HiFill, 1#/sk Capseal, .3% HR-7, 11.0 ppg, 3.82 cu ft/sk; 535 sx 50-50 Poz, 2% gel, 10% salt, .6% Halad 24, 1/4#/sk Flocele, 1#/sk Capseal, 14.1 ppg, 1.32 cu ft/sk. Drop plug, displace w/147 bbls water. Bump plug w/1900 psi @ 2:23 a.m., 6/8/91. Floats held, no returns, good lift. ND BOP. Set slips w/100M#. Cut csg. Rig released 5:00 a.m., 6/8/91. CC: \$196,781. FINAL DRILLING REPORT.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

3. LEASE DENOMINATION AND SERIAL NO.

State U-01194

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

Natural Buttes Unit

8. FARM OR LEASE NAME

NBU

9. WELL NO.

#132

10. FIELD AND FURTHER IDENTIFY

Natural Buttes

11. SEC. T., R. M., OR BLK. AND TOWNSHIP OR AREA

Section 26, DIVISION OF OIL, GAS & MINING

12. COUNTY

Utah

14. API NO.

43-047-31938

DATE ISSUED

1/16/91

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1A. TYPE OF WELL:

OIL WELL GAS WELL DRY Other _____

1B. TYPE OF COMPLETION:

NEW WELL WORK OVER DEEP-EN PLUG BACK DIFF. RESVR. Other _____

2. NAME OF OPERATOR

Coastal Oil & Gas Corporation

3. ADDRESS OF OPERATOR

P. O. Box 749, Denver, Colorado 80201-0749 (303) 573-4476

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 594' FNL & 850' FWL (NWNW)

At top prod. interval reported below Same as above

At total depth Same as above



AUG 12 1991

15. DATE SPUDDED

4/1/91

16. DATE T.S. REACHED

6/6/91

17. DATE COMPL. (Ready to prod.)

6/13/91

(Plng & Abd.)

18. ELEVATIONS (DP, HEB, AT, CR, ETC.)

4963' GR, 4975' KB

12. COUNTY

Utah

Section 26, DIVISION OF OIL, GAS & MINING

12. COUNTY

Utah

20. TOTAL DEPTH, MD & TVD

6377'

21. PLUG BACK T.S., MD & TVD

6368'

22. IF MULTIPLE COMPL. HOW MANY

23. INTERVALS DRILLED BY

ROTARY TOOLS

SFC-TD

CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)

5014-6332' Wasatch

25. WAS DIRECTIONAL SURVEY MADE

NO

26. TYPE ELECTRIC AND OTHER LOGS RUN

DLL, CDL/DSN, CBL *Borehole Profile 6-20-91*

27. WAS WELL CORED YES NO (Submit analysis)
DRILL STEM TEST YES NO (See reverse side)

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8-5/8"	24#	270'	12-1/4"	180 sx Prem "G" + add	NONE
5-1/2"	17#	6376'	7-7/8"	745 sx HiFill + 50/50 POZ 58 BBLs cmt (See chrono for Bullhead squeeze.)	NONE

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	PACKER CEMENT	SCREEN (MD)	30. TUBING RECORD
					SIZE DEPTH SET (MD) PACKER SET (MD)

31. PERFORATION RECORD (Interval, size and number)

Perforate w/4" csg gun @ following depths

DEPTH	START	STOP	DEPTH
5014'	5448'	5888'	6195'
5018'	5476'	5892'	6227'
5060'	5740'	5902'	6293'
5064'	5744'	6040'	6332'
5069'	5749'	6188'	

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
5014-6332'	4000 gals 3% KCL wtr + 38 B.S.

33. PRODUCTION

DATE FIRST PRODUCTION	PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)	WELL STATUS (Producing or shut-in)					
6/12/91	Flowing	SI					
DATE OF TEST	HOURS TESTED	CHOSE SIZE	PROD. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
6/13/91	24	20/64"	→	0	500	0	N/A
FLOW, TUBING PRBL.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
195	250	→	0	500	0	N/A	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

SIWOPLC

TEST WITNESSED BY

D. Barone

35. LIST OF ATTACHMENTS

Chronological History

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

Eileen Danni Dey
Eileen Danni Dey

Regulatory Analyst

DATE 8/8/91

See Spaces for Additional Data on Reverse Side

INSTRUCTIONS

This form should be completed in compliance with the Utah Oil and Gas Conservation General Rules. If not filed prior to this time, all logs, tests, and directional surveys as required by Utah Rules should be attached and submitted with this report.

ITEM 16: Indicate which elevation is used as reference for depth measurements given in other spaces on this form and on any attachments.
 ITEMS 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

ITEM 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

ITEM 33: Submit a separate completion report on this form for each interval to be separately produced (see instruction for items 22 and 24 above).

37. SUMMARY OF POROUS ZONES:		38. GEOLOGIC MARKERS	
Formation	Top	Bottom	Description, contents, etc.
			<p>Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.</p>
			<p>Wasatch Fm</p>
			<p>Meas. Depth 4760'</p>
			<p>Top True Vert. Depth 4760'</p>

COASTAL OIL & GAS CORPORATION
CHRONOLOGICAL HISTORY

NBU #132
NATURAL BUTTES UNIT
UINTAH COUNTY, UTAH
COASTALDRIL #1
WI: 100% COGC AFE: 13014
ATD: 6200' (WASATCH) SD: 5/31/91
CSG: 8-5/8" @ 270'
DHC(M\$): 158.9

NW/NW SECTION 26-T9S-R21E

- 4/3/91 260' MIRU Leon ross. Spud @ 11:00 a.m., 4/1/91. Drill 12-1/4" hole to 260'. run 6 jts 8-5/8" 24# K-55 ST&C (256.94') & set @ 258'. Equipped w/guide shoe and 3 centralizers. Cmt w/180 sx prem "G" w/2% CaCl₂ & 1/4#/sx Flocele. Wt 15.6#/gal, Yd 1.18 cu ft/sx. Drop plug and displ w/14.5 BFW. SD 12:04 p.m., 4/2/91. Good returns, circ 6 bbls cmt to pit. Drill rat & mouse hole. CC: \$23,126.
- 6/1/91 900' Drlg 630'/7-1/2 hrs. Spud @ 10:00 p.m., 5/31/91. NU BOP's, test to 2000 psi, hydril and csg to 1500 psi, OK. PU BHA, drill cmt plug & shoe, tag cmt @ 240'. Drlg, svy: 1-1/4 deg @ 795'. Drlg w/mist. pH 12.0, air 1400 SCFM. CC: \$60,623.
- 6/2/91 2675' Drlg 1775'/22.5 hrs. Drlg, svys: 1 deg @ 1301'; 1-1/4 deg @ 2309'. Start aerated @ 1824', water @ 1755'. Drlg w/aerated wtr, pH 11.0, 700 CFM. CC: \$69,701.
- 6/3/91 3640' Drlg 965'/18.5 hrs. Drlg, svy: 1-3/4 deg @ 3132'. TFNB, work BOP's. Wash & ream 70' to btm, no fill. Drlg w/aerated wtr. pH 10.5, 700 CFM. CC: \$80,577.
- 6/4/91 4600' Drlg 960'/23 hrs. Drlg, RS, chk BOP. Drlg, svy: 1-3/4 deg @ 4203'. Drlg w/wtr. MW 8.4, VIS 27, WL N/C, PH 10.5. CC: \$89,017.
- 6/5/91 5340' Drlg 740'/23 hrs. Drlg, RS, check BOP. Drlg w/aerated wtr. Svy: 3-3/4 deg @ 5245'. MW 8.4, VIS 27, WL 10.5, 700 SCFM & 40 SPM. CC: \$97,621.
- 6/6/91 5936' Drlg 596'/23 hrs. Drlg, RS, check BOP. Svy: 3 deg @ 5560'. Drlg w/aerated wtr. MW 8.4, VIS 27, WL N/C, PH 10.5, 600 SCFM. CC: \$103,731.
- 6/7/91 6377' RU Howco (HLS) to run E logs. 441'/16-1/2 hrs. Drlg, RS, check BOP. Drlg, circ & cond hole. Short trip 15 stds - OK. Displace hole w/500 bbls 10 ppg brine. Drop svy, TOOH, SLM. Strap 6375.30', no correction. RU HLS. Run DIL-GR Caliper-CNL-FDC. Drlg brks from 5734-5747'; 5879-5902'; 6182-6193'; 6285-6307'; 6324-6331'. Drlg w/aerated wtr. Svy: 2-3/4 deg @ 6352'. MW 8.4, VIS 27, WL N/C, PH 11.0, 600 SCFM. CC: \$112,418.
- 6/8/91 6377' RDRT Logging w/HLS. Ran DIL-GR-Cal-FDC-GR to surface; CNL-FDC to 2700'; logger's TD 6380'. BHT 153°F. TIH, RU csg crew, LD DP. Run 155 jts (6383.09') 5-1/2" 17# J-55 LT&C. FS @ 6376'; FC @ 6333', 10 centralizers. RU Howco, wash to 6362', bridge @ 6362'. Cmt w/210 sx HiFill, 1#/sk Capseal, .3% HR-7, 11.0 ppg, 3.82 cu ft/sk; 535 sx 50-50 Poz, 2% gel, 10% salt, .6% Halad 24, 1/4#/sk Flocele, 1#/sk Capseal, 14.1 ppg, 1.32 cu ft/sk. Drop plug, displace w/147 bbls water. Bump plug w/1900 psi @ 2:23 a.m., 6/8/91. Floats held, no returns, good lift. ND BOP. Set slips w/100M#. Cut csg. Rig released 5:00 a.m., 6/8/91. CC: \$196,781. FINAL DRILLING REPORT.

THE COASTAL CORPORATION
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

NBU #132
NW/NW SECTION 26-T9S-R21E
NATURAL BUTTES UNIT
UINTAH COUNTY, UTAH
WI: 100% COGC AFE: 13014
TD: 6377' (WASATCH) SD: 5/31/91
CSG: 5-1/2" @ 6376'
PERFS: 5014'-6332'
CWC(M\$): \$358.8

Page 2

6/11/91 MIRU Welltech.
DC: \$19,000 TC: \$215,781

6/12/91 Prep to log. TIH w/mill on 2-3/8" tubing. Tag cmt @ 6344'. RU power swivel. Drill out to 6368'. Circ hole clean w/3% KCl. POOH w/tbg.
DC: \$1,850 TC: \$217,631

6/13/91 Flow testing well. MIRU Cutters. Run CBL from 6368' to 900'. TOC @ 1070'. TIH w/4" csg gun. Perf Wasatch w/19 holes from 5014' to 6332'. MIRU Western. Breakdown Wasatch w/4000 gals 3% KCl water. AIP 4200 psi, AIR 5.8 BPM. ISIP 1400 psi, 15 min 1200 psi. RD Western. Open well. Flow 18 bbls. Swab 58 bbls. Well started flowing. Flowing 330 MCFD, 135 psi FTP, 20/64" choke.
DC: \$7,220 TC: \$224,851

6/14/91 Prep to kill well. Flowing 500 MCFD, 195 psi FTP, 20/64" choke.
DC: \$900 TC: \$225,751

6/15/91 SI, waiting on frac. Kill well w/100 bbls 3% KCl. POOH w/tbg. LD tbg. ND BOP, NU tree. RDMO CU.
DC: \$1,280 TC: \$227,031

6/16/91 SI, waiting on frac. MIRU Western. Pump 20 bbl LCM pill down 8-5/8" x 5-1/2" annulus. Mix and pump 25 bbl lead cmt and 13 bbl tail cmt. Caught pressure. Squeezed to 700 psi. Cmt to surface. Drop from report until further activity.
DC: \$6,313 TC: \$233,344

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Lease Designation and Serial Number

State #U-01194

7. Indian Allottee or Tribe Name

N/A

8. Unit or Communitization Agreement

Natural Buttes Unit

9. Well Name and Number

NBU # 132

10. API Well Number

43-047-31938

11. Field and Pool, or Wildcat

Natural Buttes

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT— for such proposals.

1. Type of Well

Oil Well Gas Well Other (specify)

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address of Operator

P.O. Box 749, Denver, Colorado 80201-0749

4. Telephone Number
(303) 573-4476

5. Location of Well

Footage 594' FNL & 850' FWL
Co. Sec. T. R. M. : NWNW Section 26, T9S-R21E

County : Uintah
State : UTAH

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

- Abandonment
- Casing Repair
- Change of Plans
- Conversion to Injection
- Fracture Treat
- Multiple Completion
- Other Pipeline Right-of-Way
- New Construction
- Pull or Alter Casing
- Recompletion
- Shoot or Acidize
- Vent or Flare
- Water Shut-Off

Approximate Date Work Will Start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- Abandonment
- Casing Repair
- Change of Plans
- Conversion to Injection
- Fracture Treat
- Other
- New Construction
- Pull or Alter Casing
- Shoot or Acidize
- Vent or Flare
- Water Shut-Off

Date of Work Completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Coastal Oil & Gas Corporation requests a right-of-way to install a 4" gas pipeline from the NBU # 132 gas well and tie into the existing gas pipeline. This right-of-way will be located in section 26, T9S -R21E, within lease #U-01194 and within the Natural Buttes Unit boundaries. Coastal requests a 30' width easement with a total slope distance of 1072'. There will be minimum surface disturbance as the pipeline will be laid on the surface. Please see the attached topographic map which illustrates this proposed right-of-way.

RECEIVED

SEP 26 1991

DIVISION OF
OIL GAS & MINING

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

11-4-91

JM Matthews

14. I hereby certify that the foregoing is true and correct

Name & Signature

Calvin Ramirez

Title Regulatory Analyst Date 9-24-91

(State Use Only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Lease Designation and Serial Number	State U-01194
7. Indian Allottee or Tribe Name	N/A
8. Unit or Communitization Agreement	Natural Buttes Unit
9. Well Name and Number	NBU #132
10. API Well Number	43-047-31938
11. Field and Pool, or Wildcat	Natural Buttes

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter, plugged, and abandoned wells.
Use APPLICATION FOR PERMIT— for such proposals.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)
2. Name of Operator Coastal Oil & Gas Corporation
3. Address of Operator P. O. Box 749 Denver, CO 80201-0749
4. Telephone Number (303) 573-4476
5. Location of Well Footage 594' FNL & 850' FWL Q. Q. Sec. T. R. M. : NW/NW Section 26, T9S-R21E County : Uintah State : UTAH

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit in Duplicate)

- Abandonment
- Casing Repair
- Change of Plans
- Conversion to Injection
- Fracture Treat
- Multiple Completion
- Other
- New Construction
- Pull or Alter Casing
- Recompletion
- Shoot or Acidize
- Vent or Flare
- Water Shut-Off

Approximate Date Work Will Start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- Abandonment
- Casing Repair
- Change of Plans
- Conversion to Injection
- Fracture Treat
- Other
- New Construction
- Pull or Alter Casing
- Shoot or Acidize
- Vent or Flare
- Water Shut-Off

Date of Work Completion 11/25/91

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.
Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please see the attached chronological history for the fracture treatment procedure performed on the above referenced well.

RECEIVED

JAN 17 1992

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name & Signature Gillean Danni Key Title Regulatory Analyst Date 1/13/92

(State Use Only) Gillean Danni Key

THE COASTAL CORPORATION
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

NBU #132
NW/NW SECTION 26-T9S-R21E
NATURAL BUTTES UNIT
UINTAH COUNTY, UTAH
WI: 100% COGC AFE: 13014
TD: 6377' (WASATCH) SD: 5/31/91
CSG: 5-1/2" @ 6376'
PERFS: 5014'-6332'
CWC(M\$): \$358.8

Page 2

11/3/91 Prep to run tbq. MIRU Pool #298. Killed well w/250 bbls 3% KCl wtr. ND WH, NU BOP. PU & RIH w/79 jts 2-3/8" tbq.
DC: \$3,650 TC: \$236,994

11/4/91 SI, WO frac. Blew down well. Finish RIH w/tbg. Total tbq 159 jts set @ 4964' w/notched collar on btm, SN 1-jt above btm and 10' blast joint on top. ND BOP, NU WH. RDMO CU.
DC: \$15,800 TC: \$252,794

11/12/91 Flow back after frac. MIRU Smith. Frac Wasatch perfs w/195,000 gals gelled KCl wtr w/352,000# sand and 30% CO₂. Pump pad, pump 1 to 6 ppg sand in 5 stages. Drop 10 ball sealers. Pump pad, pump 1 to 6 ppg sand in 5 stages. ISIP 1640 psi, 15 min 1720 psi, AIR 35 BPM @ 3950 psi 1st frac, 28 BPM @ 4150 psi 2nd frac.
DC: \$122,746 TC: \$375,540

11/13/91 Flowing 1400 MCFD CO₂, FTP 1000 psi, CP 700 psi, 16/64" choke, 10 BWP.

11/14/91 Flowing 2200 MCFD CO₂, FTP 1000 psi, CP 1125 psi, 20/64" choke, 10-20 BWP.

11/15/91 Flowing 2000 MCFD CO₂, FTP 1550 psi, CP 1325 psi, 16/64" choke, 15 BWP.

11/16/91 Flowing 2300 MCFD CO₂, FTP 1575 psi, CP 1150 psi, 16/64" choke, 30 BWP.

11/17/91 Flowing 2400 MCFD, FTP 1600 psi, CP 1100 psi, 16/64" choke, 5 BWP. Gas will burn.

11/18/91 SI, WOPLC.

11/22/91 Prep to CO frac sand. MIRU Pool. Kill well w/200 bbls 3% KCl wtr. ND WH, NU BOP. PU & RIH w/2-3/8" tbq. Tagged sand @ 6130'. PU above perfs.
DC: \$4,070 TC: \$379,610

11/23/91 Prep to swab. Killed well w/200 bbls 3% KCl wtr. PU & RIH w/2-3/8" tbq. Circ out frac sand from 6130' to PBTD. Pull tbq back to 4964'. ND BOP, NU WH. SDFN.
DC: \$2,490 TC: \$382,100

11/24/91 Flow to pit. Tree froze. Thaw out tree. Flowing 1700 MCFD, FTP 700 psi, CP 875 psi, 20 BWP.
DC: \$1,000 TC: \$383,100

11/25/91 SI, WOPLC. Flowing 3200 MCFD, FTP 1400 psi, CP 1400 psi, 20/64" choke. RDMO Pool. Drop from report until further activity.
DC: \$1,500 TC: \$384,600

RECEIVED

JAN 17 1992

DIVISION OF
OIL GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

6. Lease Designation and Serial Number State U-01194
7. Indian Allottee or Tribe Name N/A
8. Unit or Communitization Agreement Natural Buttes Unit
9. Well Name and Number NBU #132
10. API Well Number 43-047-31938
11. Field and Pool, or Wildcat Natural Buttes

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT for such proposals.

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify)	
2. Name of Operator Coastal Oil & Gas Corporation	
3. Address of Operator P. O. Box 749 Denver, CO 80201-0749	
4. Telephone Number (303) 573-4476	
5. Location of Well Footage : 594' FNL & 850' FWL QQ. Sec. T., R., M. : NW/NW Section 26, T9S-R21E County : Uintah State : UTAH	

12. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA.

NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandonment	<input type="checkbox"/> Abandonment
<input type="checkbox"/> Casing Repair	<input type="checkbox"/> Casing Repair
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Change of Plans
<input type="checkbox"/> Conversion to Injection	<input type="checkbox"/> Conversion to Injection
<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Fracture Treat
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Other Report of 1st Sales
<input type="checkbox"/> Other	
<input type="checkbox"/> New Construction	<input type="checkbox"/> New Construction
<input type="checkbox"/> Pull or Alter Casing	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Recompletion	<input type="checkbox"/> Shoot or Acidize
<input type="checkbox"/> Shoot or Acidize	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Vent or Flare	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Water Shut-Off	

Approximate Date Work Will Start _____

Date of Work Completion 12/20/91

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.
* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The above referenced well was connected to CIG's gas salesline and 1st sales occurred @ 9:45 a.m., 12/20/91 with a rate of 2230 MCFD, FTP 1978 psi, SICP 1967 psi on 16/64" choke.

RECEIVED

JAN 27 1992

DIVISION OF
OIL GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name & Signature

Eileen Barrie Day

Title Regulatory Analyst

Date 1/22/92

(State Use Only)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

APR 17 1992

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS
DIVISION OF OIL GAS & MINING

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
 Coastal Oil & Gas Corporation

3. Address and Telephone No.
 P. O. Box 749 Denver, CO 80201-0749 (303) 573-4476

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
 See Attached List

5. Lease Designation and Serial No.
 See Attached List

6. If Indian, Allottee or Tribe Name
 See Attached List

7. If Unit or CA, Agreement Designation
 Natural Buttes Unit

8. Well Name and No.
 See Attached List

9. API Well No.
 See Attached List

10. Field and Pool, or Exploratory Area
 Natural Buttes

11. County or Parish, State
 Uintah County, Utah

12 CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Abandonment
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Recompletion
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Plugging Back
	<input type="checkbox"/> Casing Repair
	<input type="checkbox"/> Altering Casing
	<input checked="" type="checkbox"/> Other NTL 2B; IV
	<input type="checkbox"/> Change of Plans
	<input type="checkbox"/> New Construction
	<input type="checkbox"/> Non-Routine Fracturing
	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Conversion to Injection
	<input type="checkbox"/> Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Coastal Oil & Gas Corporation hereby requests permission to dispose of produced water in unlined pits per NTL-2B, IV, for the subject wells.

- 1) These wells are completed in the Wasatch formation and produce less than 5 barrels of water per day on a monthly basis.
- 2) Two unlined pits per location will be used due to the size and layout of the locations: 40' x 40' x 8' and 6' x 6' x 6' deep with berms surrounding them. Each pit will be fenced and will have cement corner posts per BLM specifications. (See the attached typical facilities diagram.)
- 3) The average evaporation rate for the area compensated for annual rainfall is 70" per year.
- 4) The estimated percolation rate based on the soil characteristics under and adjacent to the pits is 2-6" per hour.
- 5) The depth of usable water aquifers in this area is approximately 1500'.

14. I hereby certify that the foregoing is true and correct.

Signed Eileen Dana DeW
(This space for Federal or State office use)

Title Regulatory Analyst

Date 4/14/92


Approved by _____
Conditions of approval, if any:

Title _____

Accepted by the State
of Utah Division of
Oil, Gas and Mining
Date: 4-29-92

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

COASTAL OIL & GAS CORP.
NATURAL BUTTES UNIT
TYPICAL FACILITIES LAYOUT
NTL-2B; IV



13-Apr-92

NATURAL BUTTES

UINTAH COUNTY, UTAH

WELL #	LOCATION			RGE	STATE OR BLM		API NUMBER
	QUAD	SEC	TWP		LEASE #	SURFACE	
NBU #103	SENW	10	9	21	U-0141315	UTE	43-047-31956
NBU #104	SENE	16	9	21	ST ML-3282	UTE	43-047-31957
NBU #105	SWSW	17	9	21	U-0575	UTE	43-047-31955
NBU #106	NESW	21	9	21	U-0576	UTE	43-047-31946
NBU #107	SENW	26	9	21	ST ML-01194	STATE	43-047-31916
NBU #108	SESE	19	9	22	U-0284	UTE	43-047-31958
NBU #109	SENE	27	9	21	ST U-01194-A	STATE	43-047-31917
NBU #110	NENE	28	9	21	U-0576	FED.	43-047-31924
NBU #111	SWNW	25	9	21	ST U-01194	STATE	43-047-31920
NBU #112	SESE	33	9	22	U-01191	FED.	43-047-31930
NBU #113	SESE	34	9	22	U-0149077	FED.	43-047-31931
NBU #114	SWSW	5	10	21	U-01393-D	FED.	43-047-31923
NBU #115	NENW	10	10	21	U-0149079	FED.	43-047-31929
NBU #116	NWNW	6	10	22	U-464	FED.	43-047-31925
NBU #117	NENE	10	10	22	ST UT-01197-A	STATE	43-047-31914
NBU #118	SENE	22	9	20	U-0577-B	UTE	43-047-31969
NBU #119	SENW	22	9	20	U-0577-B	UTE	43-047-31973
NBU #120	NWNW	10	9	21	U-0141315	UTE	43-047-31972
NBU #121	NWNE	13	9	21	U-01193	UTE	43-047-
NBU #122	SWSE	13	9	21	U-01193	UTE	43-047-32085
NBU #123	NWNW	15	9	21	U-01188	UTE	43-047-31974
NBU #124	NWNE	16	9	21	ST ML-3282	UTE	43-047-31971
NBU #125	NESE	17	9	21	U-0575	UTE	43-047-32090
NBU #126	NENW	21	9	21	U-0576	UTE	43-047-31962
NBU #127	SWNW	21	9	21	U-0576	UTE	43-047-31963
NBU #128	SWSW	21	9	21	U-0576	UTE	43-047-31964
NBU #129	SENE	22	9	21	U-010950-A	UTE	43-047-31965
NBU #130	SWNW	22	9	21	U-0147566	UTE	43-047-31967
NBU #131	NWSW	23	9	21	U-0149075	UTE	43-047-31966
NBU #132	NWNW	26	9	21	ST U-01194	STATE	43-047-31938
NBU #133	SWNE	28	9	21	U-0576	FED.	43-047-31950
NBU #134	SWSW	28	9	21	U-0576	FED.	43-047-32011
NBU #135	NESE	18	9	22	U-461	UTE	43-047-32089
NBU #136	SWSE	19	9	22	U-0284	UTE	43-047-31968
NBU #137	SESE	30	9	22	ST ML-22935	STATE	43-047-31939
NBU #138A	SENE	33	9	22	U-01191-A	FED.	43-047-32151
NBU #139	SWNE	14	10	21	U-465	FED.	43-047-31948
NBU #140	NWNE	5	10	22	U-01191A	FED.	43-047-31947
NBU #141	SENW	6	10	22	U-464	FED.	43-047-32017
NBU #142	NESE	10	10	22	U-025187	FED.	43-047-32013
NBU #143	NWNE	10	9	21	U-0141315	UTE	43-047-32088
NBU #144	NWNW	23	9	21	U-0149075	UTE	43-047-32044
NBU #145	NWNE	27	9	21	ST U-01194-A	STATE	43-047-31976
NBU #146	SWNW	14	10	21	U-465	FED.	43-047-31985
NBU #147	NWSW	4	10	22	U-01191	FED.	43-047-31984
NBU #148	SESW	4	10	22	U-01191	FED.	43-047-31983
NBU #149	NESE	5	10	22	U-01191	FED.	43-047-31982
NBU #150	SENW	9	10	22	U-01196-B	FED.	43-047-31992
NBU #151	NWNW	9	10	22	U-01196-B	FED.	43-047-31991
NBU #152	SESE	9	10	22	U-01196-D	FED.	43-047-31990
NBU #153	SWNW	11	10	22	ST U-01197-A	STATE	43-047-31975
NBU #154	NWSE	26	9	21	ST ML-22934	STATE	43-047-32003
NBU #155	SENW	31	9	22	ST ML-23607	STATE	43-047-32004
NBU #156	SWNW	35	9	21	ST U-01194	STATE	43-047-32005
NBU #157	SESW	32	9	22	ST ML-22649	STATE	43-047-32007
NBU #158	NWSE	27	9	21	ST U-01194-A	STATE	43-047-31997
NBU #159	NESW	35	9	21	ST U-01194	STATE	43-047-31996
NBU #160	SESW	31	9	22	ST ML-22935-A	STATE	43-047-32006
NBU #161	SESE	32	9	22	ST ML-22649	STATE	43-047-32023
NBU #162	SENW	12	10	20	U-4478	FED.	43-047-32066
NBU #163	NENW	14	10	21	U-465	FED.	43-047-32069
NBU #164	NWSE	3	10	22	U-01191-A	FED.	43-047-32055
NBU #165	NENW	3	10	22	U-01191	FED.	43-047-32057
NBU #166	SWSE	28	9	21	U-0576	FED.	43-047-32065
NBU #167	SESW	25	9	21	ST U-01194	STATE	43-047-32054
NBU #168	NWSW	12	10	20	U-4478	FED.	43-047-32117
NBU #169	SESW	12	10	20	U-4478	FED.	43-047-32118

13-Apr-92

NATURAL BUTTES

UINTAH COUNTY, UTAH

WELL #	LOCATION			RGE	STATE OR BLM		API NUMBER
	QUAD	SEC	TWP		LEASE #	SURFACE	
NBU #170	NWNW	4	10	22	U-01191-A	FED.	43-047-32169
NBU #171	SENE	5	10	22	U-01191-A	FED.	43-047-32115
NBU #172	NENE	19	9	22	U-0284	UTE	43-047-32194
NBU #173	NWNE	33	9	22	U-01191-A	FED.	43-047-32116
NBU #174	NWNW	11	9	21	U-0141315	UTE	43-047-32193
NBU #175	NENW	28	9	21	U-0576	FED.	43-047-32143
NBU #176	SWNW	28	9	21	U-0576	FED.	43-047-32144
NBU #177	NESE	29	9	21	U-0581	FED.	43-047-32112
NBU #178	NWNE	30	9	21	U-0581	FED.	43-047-32121
NBU #179	SWSW	10	10	21	U-01416-A	FED.	43-047-32145
NBU #180	SWSE	10	10	22	U-025187	FED.	43-047-32113
NBU #181	SESW	9	9	21	U-0576	UTE	43-047-32161
NBU #182	SENW	11	9	21	U-0141315	UTE	43-047-32162
NBU #183 ✓	SWNW	27	9	21	ST U-01194-A	STATE	43-047-32122
NBU #184	SESW	30	9	22	U-463	FED.	43-047-32170
NBU #185	SWNE	3	10	22	U-01191-A	FED.	43-047-32171
NBU #186	SENE	30	9	22	U-463	FED.	43-047-
NBU #187	SESW	34	9	22	U-0149077	FED.	43-047-
NBU #188	SWSW	10	10	22	U-01196-C	FED.	43-047-
NBU #189	SESW	23	9	21	U-0149075	UTE	43-047-
NBU #190 ✓	NWNE	26	9	21	ST U-01194	STATE	43-047-
CIGE 110-7-9-21	SWSE	7	9	21	U-0575-B	UTE	43-047-31959
CIGE 111-13-9-21	SESW	13	9	21	U-01193	UTE	43-047-31954
CIGE 112-19-9-21	SESE	19	9	21	U-0581	UTE	43-047-31945
CIGE 113-21-9-21	SWNE	21	9	21	U-0576	UTE	43-047-31944
CIGE 114-34-9-21 ✓	NESE	34	9	21	ST U-01194-A	STATE	43-047-31915
CIGE 115-35-9-21 ✓	NWNE	35	9	21	ST ML-22582	STATE	43-047-31918
CIGE 116-29-9-22 ✓	NWSW	29	9	22	ST ML-22935	STATE	43-047-31919
CIGE 117-34-9-22	SWNW	34	9	22	U-0149077	FED.	43-047-31928
CIGE 118-35-9-22	NESE	35	9	22	U-010954A	FED.	43-047-32025
CIGE 119-15-10-21	NENE	15	10	21	U-01416-A	FED.	43-047-31927
CIGE 120-15-9-20	SENE	15	9	20	U-0144868	UTE	43-047-32032
CIGE 121-15-9-20	NWNE	15	9	20	U-0144868	UTE	43-047-32031
CIGE 122-7-9-21	NENE	7	9	21	U-0149767	UTE	43-047-32098
CIGE 123-7-9-21	SWNE	7	9	21	U-0575-B	UTE	43-047-32047
CIGE 124-9-9-21	NWSE	9	9	21	U-01188	UTE	43-047-32045
CIGE 125-13-9-21	NWNW	13	9	21	U-01193	UTE	43-047-32084
CIGE 126-13-9-21	NWSW	13	9	21	U-01193	UTE	43-047-32087
CIGE 127-16-9-21	NESW	16	9	21	ST ML-3141	UTE	43-047-32036
CIGE 128-18-9-21	NENE	18	9	21	U-0575	UTE	43-047-32046
CIGE 129-18-9-21	NENW	18	9	21	U-0581	UTE	43-047-32043
CIGE 130-19-9-21	NENE	19	9	21	U-0581	UTE	43-047-32030
CIGE 131-19-9-21	SWNE	19	9	21	U-0581	UTE	43-047-32029
CIGE 132-20-9-21	NWSW	20	9	21	U-0575	UTE	43-047-32028
CIGE 133-35-9-21 ✓	SWSE	35	9	21	ST ML-22582	STATE	43-047-31978
CIGE 134-1-10-20	SWSW	1	10	20	U-02270-A	FED.	43-047-31989
CIGE 135-3-10-21	SWSW	3	10	21	U-0149078	FED.	43-047-32001
CIGE 136-4-10-21 ✓	SWNE	4	10	21	ST ML-22940	STATE	43-047-31979
CIGE 137-6-10-21	SENE	6	10	21	U-01791	FED.	43-047-31988
CIGE 138A-6-10-21	SENW	6	10	21	U-01791	FED.	43-047-31987
CIGE 139-10-10-21	SWNE	10	10	21	U-0149079	FED.	43-047-31986
CIGE 140-16-10-21 ✓	NENE	16	10	21	ST ML-10755	STATE	43-047-31977
CIGE 141-7-10-22 ✓	NWNE	7	10	22	ST ML-23609	STATE	43-047-31970
CIGE 142-25-9-21 ✓	SENE	25	9	21	ST U-01189	STATE	43-047-31994
CIGE 143-34-9-21 ✓	SWNE	34	9	21	ST U-01194-A	STATE	43-047-31995
CIGE 144-2-10-22 ✓	SWNE	2	10	22	ST ML-22651	STATE	43-047-32022
CIGE 145-29-9-22 ✓	SENW	29	9	22	ST ML-22935	STATE	43-047-31993
CIGE 146-16-10-21 ✓	NWNE	16	10	21	ST ML-10755	STATE	43-047-32021
CIGE 147-36-9-22 ✓	SESW	36	9	22	ST ML-22650	STATE	43-047-32020
CIGE 148-31-9-22 ✓	NWNE	31	9	22	ST ML-22935-A	STATE	43-047-32024
CIGE 149-8-10-21	NWNE	8	10	21	U-01791	FED.	43-047-32056
CIGE 150-9-10-21	SWNE	9	10	21	U-01416	FED.	43-047-32058
CIGE 151-10-10-21	SWSE	10	10	21	U-0149079	FED.	43-047-32059
CIGE 152-33-9-22	SESW	33	9	22	U-01191-A	FED.	43-047-32068
CIGE 153-35-9-22	SESW	35	9	22	U-010954-A	FED.	43-047-32067
CIGE 154-13-10-20	NWNW	13	10	20	U-4485	STATE	43-047-32119
CIGE 155-9-9-21	SENE	9	9	21	U-01188-B	UTE	43-047-32157

13-Apr-92

NATURAL BUTTES

UINTAH COUNTY, UTAH

WELL #	LOCATION			STATE OR BLM		SURFACE	API NUMBER
	QUAD	SEC	TWP	RGE	LEASE #		
CIGE 156-16-9-21	NESE	16	9	21	ST ML-3282	UTE	43-047-32195
CIGE 157-16-9-21	SWNW	16	9	21	U-38409	UTE	43-047-32160
CIGE 158-21-9-21	NESE	21	9	21	U-0576	UTE	43-047-32158
CIGE 159-6-10-21	NWNE	6	10	21	U-01791	FED.	43-047-32120
CIGE 160-14-10-21	SWSE	14	10	21	U-01393-C	FED.	43-047-32124
CIGE 161-2-10-22	SESE	2	10	22	ST ML-22651	STATE	43-047-32168
CIGE 162-36-9-22	SESE	36	9	22	ST ML-22650	STATE	43-047-32164
CIGE 163-15-9-21	SENE	15	9	21	U-01193	UTE	43-047-32192
CIGE 164-34-9-22	NWNE	34	9	22	U-0149077	FED.	43-047-32141
CIGE 165-1-10-20	SWNW	1	10	20	U-02270-A	FED.	43-047-32114
CIGE 166-3-10-21	NENW	3	10	21	U-0149078	FED.	43-047-32172
CIGE 167-7-10-21	NENE	7	10	21	U-01791	FED.	43-047-32142
CIGE 168-16-10-21	NWSE	16	10	21	ST ML-10755	STATE	43-047-32123
CIGE 169-2-10-21	SENE	2	10	21	ST ML-22652	STATE	43-047-

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER:		5. Lease Designation and Serial Number: See attached list
2. Name of Operator: Coastal Oil and Gas Corporation		6. If Indian, Allottee or Tribe Name: See attached list
3. Address and Telephone Number: P.O. Box 749, Denver, CO 80201-0749 (303) 573-4476		7. Unit Agreement Name: Natural Buttes Unit
4. Location of Well Footages: See attached list. County: Uintah QQ, Sec., T., R., M.: State: Utah		8. Well Name and Number: See attached list
		9. API Well Number: See attached list
		10. Field and Pool, or Wildcat: Natural Buttes

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT
(Submit In Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recompletion |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>Install telemetry equipment</u> | |

Approximate date work will start 9/27/94

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Date of work completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.


* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The operator requests permission to install automatic gauging and gas sales optimization equipment on the listed wells.

The installation will consist of GH Flow's "Automate," a remote gas flow computer which includes electronic gas measurement. Also, a tank level alarm, tubing and casing pressure, and an automatic choke will be installed on some of the listed wells for gas flow sales optimization and labor reduction. Some wells will have temperature alarms installed on the separator and dehydrator to prevent a high-cost major failure. Wells with intermitters will be controlled with the GH Flow Automate RTU instead of the existing mechanical timer.

**Accepted by the
Utah Division of
Oil, Gas and Mining**



FOR RECORD ONLY

13. Name & Signature: Bonnie Johnston

Title: Environmental Coordinator Date: 09/09/94

(This space for State use only)

Well	Lease Designation & Serial Number	If Indian, Allottee or Tribe Name	API #	Location of Well At Surface	Section, Township, Range
CIGE #115-35-9-21	State ML-22582	N/A	43-047-31918	509' FNL & 2338' FEL NW/NE	Sect.35, T9S-R21E
CIGE #143-34-9-21	State U-01194A	Ute Tribal Surface	43-047-31995	1811' FNL & 1624' FEL SW/NE	Sect.34, T9S-R21E
CIGE #87D-34-9-21	U-01194-A-ST	N/A	43-047-30869	967' FNL & 422' FEL NE/NE	Sect.34, T9S-R21E
NBU #132	State U-01194	N/A	43-047-31938	594' FNL & 850' FWL NW/NW	Sect.26, T9S-R21E
NBU #156	U-01194-ST	N/A	43-047-32005	1992' FNL & 774' FWL SW/NW	Sect.35, T9S-R21E

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER:		5. Lease Designation and Serial Number: See attached list
2. Name of Operator: Coastal Oil and Gas Corporation		6. If Indian, Allottee or Tribe Name: See attached list
3. Address and Telephone Number: P.O. Box 749, Denver, CO 80201-0749 (303) 573-4476		7. Unit Agreement Name: Natural Buttes Unit
4. Location of Well Footages: See attached list. QQ, Sec., T., R., M.:		8. Well Name and Number: See attached list
		9. API Well Number: See attached list
		10. Field and Pool, or Wildcat: Natural Buttes
		County: Uintah State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandonment <input type="checkbox"/> Casing Repair <input type="checkbox"/> Change of Plans <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Multiple Completion <input checked="" type="checkbox"/> Other Install telemetry equipment	<input type="checkbox"/> Abandonment * <input type="checkbox"/> Casing Repair <input type="checkbox"/> Change of Plans <input type="checkbox"/> Conversion to Injection <input type="checkbox"/> Fracture Treat <input type="checkbox"/> Other
<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recompletion <input type="checkbox"/> Shoot or Acidize <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Shoot or Acidize <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off
Approximate date work will start <u>9/27/94</u>	Date of work completion _____
	Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.
	* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The operator requests permission to install automatic gauging and gas sales optimization equipment on the listed wells.

The installation will consist of GH Flow's "Automate," a remote gas flow computer which includes electronic gas measurement. Also, a tank level alarm, tubing and casing pressure, and an automatic choke will be installed on some of the listed wells for gas flow sales optimization and labor reduction. Some wells will have temperature alarms installed on the separator and dehydrator to prevent a high-cost major failure. Wells with intermitters will be controlled with the GH Flow Automate RTU instead of the existing mechanical timer.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**



13. Name & Signature: Bonnie Johnston Title: Environmental Coordinator Date: 09/09/94

(This space for State use only)

Well	Lease Designation & Serial Number	If Indian, Allottee or Tribe Name	API #	Location of Well At Surface	Section, Township, Range
CIGE #115-35-9-21	State ML-22582	N/A	43-047-31918	509' FNL & 2338' FEL NW/NE	Sect.35, T9S-R21E
CIGE #143-34-9-21	State U-01194A	Ute Tribal Surface	43-047-31995	1811' FNL & 1624' FEL SW/NE	Sect.34, T9S-R21E
CIGE #87D-34-9-21	U-01194-A-ST	N/A	43-047-30869	967' FNL & 422' FEL NE/NE	Sect.34, T9S-R21E
NBU #132	State U-01194	N/A	43-047-31938	594' FNL & 850' FWL NW/NW	Sect.26, T9S-R21E
NBU #156	U-01194-ST	N/A	43-047-32005	1992' FNL & 774' FWL SW/NW	Sect.35, T9S-R21E

5. Lease Designation and Serial Number:

U-01194

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

6. If Indian, Alutian or Tribe Name:

N/A

7. Unit Agreement Name:

Natural Buttes Unit

1. Type of Well:

OIL GAS OTHER:

8. Well Name and Number:

NBU #132

2. Name of Operator:

Coastal Oil & Gas Corporation

9. API Well Number:

43-047-31938

3. Address and Telephone Number:

P.O. Box 749, Denver, CO 80201-0749

(303) 573-4476

10. Field and Pool, or Wildcat:

Natural Buttes

4. Location of Well:

Footages: 594' FNL & 850' FWL

County: Uintah

QQ, Sec., T., R., M.: NWNW Section 26--T9S--R21E

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT

(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recompletion |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other | |

Approximate date work will start _____

SUBSEQUENT REPORT

(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Perforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>Install Siphon String</u> | |


Date of work completion 12/13/94

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please see the attached chronological history for work performed in the subject well.



13.

Name & Signature:

N.O. Shiflett

N.O. Shiflett

Title: District Drilling Manager

Date:

01/25/95

(This space for State use only)

THE COASTAL CORPORATION
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

Page 4

NBU #132 (Install siphon string)
NW/NW SECTION 26-T9S-R21E
NATURAL BUTTES UNIT
UINTAH COUNTY, UT
WI: 100% COGC AFE: 13014

10/25/94 PO: Prep to turn back into sales line. MIRU Colo. W.S. rig #26. Killed well w/60 bbls 3% KCl wtr. ND WH, NU BOP. PU & RIH w/22 jts tbg. (EOT lowered to 5660'). ND BOP, NU WH. Make 11 swb runs, rec 40 BW. IFL 4000', FFL 3000'. SICP 450 PSI. Well kicked off. Flowed overnight on 20/64" chk.
DC: \$5,620 TC: \$5,620

10/29/94 PO: SI for press BU. MI & RU Cudd coiled tbg unit. NU tbg head. RIH w/1-1/4" coiled tbg siphon string to 6100'. Set slips. NU well head & flow line. Pmpd out plug w/N₂. RD & MO Cudd.
DC: \$16,580 TC: \$16,580

11/03/94 PO: Producing. MI & RU Cudd N₂ unit, jet 1-1/4" tbg w/N₂. Flowed to pit 2 hrs. Turned into sales line @ 12:00 noon 11/02/94.
DC: \$4,640 TC: \$21,220

11/04/94 Flwg 421 MCFD; 5 BWP, est.

11/07/94 Flwg 300 MCFD; 0 BWP.

11/08/94 Flwg 385 MCFD; 2.25 BWP.

11/09/94 Flwg 392 MCFD; 0.75 BWP.

11/10/94 Flwg 321 MCF; 1.5 BW, 22 hrs.

11/11/94 Flwg 0 MCF; 0 BW, down 24 hrs.

11/17/94 Flwg 385 MCFD; 0 BWP.

11/19/94 Flwg 373 MCFD; 0.75 BWP.

11/20/94 Flwg 373 MCFD; 0 BWP.

11/21/94 Flwg 361 MCFD; 1 BWP

11/22/94 Flwg 351 MCFD; 2.25 BWP.

11/24/94 Flwg 361 MCFD; 1.0 BWP; 325# TP; 310# CP; 25/64" chk.

11/25/94 Flwg 361 MCFD; 1.0 BWP; 325# TP; 300# CP; 25/64" chk.

11/26/94 Flwg 328 MCFD; 0.75 BWP; 310# TP; 400# CP; 25/64" chk.

11/27/94 Flwg 361 MCFD; 1.50 BWP; 310# TP; 450# CP; 25/64" chk.

11/28/94 Flwg 361 MCFD; 0 BWP; 325# TP; 450# CP; 25/64" chk.

11/29/94 Flwg 361 MCFD; 0 BWP; 325# TP; 450# CP, 25/64" chk.

11/30/94 Flwg 361 MCFD; 0 BWP; 325# TP; 450# CP, 25/64" chk.

12/02/94 Flwg 361 MCFD; 0 BWP, 300# TP; 450# CP, 25/64" chk.

12/03/94 Flwg 314 MCFD, 1.5 BWP, 310# TP, 440# CP, 33/64" chk.

12/04/94 Flwg 361 MCFD, 2.25 BWP, 330# TP, 450# CP, 26/64" chk.

THE COASTAL CORPORATION
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

Page 5

NBU #132 (Install siphon string)
NW/NW SECTION 26-T9S-R21E
NATURAL BUTTES UNIT
UINTAH COUNTY, UT
WI: 100% COGC AFE: 13014

12/05/94 Flwg 361 MCFD, 0.75 BWPD, 330# TP, 450# CP, 26/64" chk.
12/06/94 Flwg 300 MCFD, 0 BWPD, 330# TP, 450# CP, 25/64" chk.
12/07/94 Flwg 349 MCFD, 0 BWPD, 340# TP, 450# CP, 26/64" chk.
12/08/94 Flwg 349 MCFD, 0.73 BWPD, 310# TP, 460# CP, 30/64" chk.
12/09/94 Flwg 349 MCFD, 2.19 BWPD, 310# TP, 460# CP, 30/64" chk.
12/10/94 Flwg 92 MCFD, 0 BWPD, 310# TP, 490# CP, 30/64" chk.
12/11/94 Flwg 349 MCFD, 0.73 BWPD, 310# TP, 480# CP, 30/64" chk.
12/12/94 Flwg 349 MCFD, 0.73 BWPD, 310# TP, 500# CP, 30/64" chk.
12/13/94 Flwg 349 MCFD, 0.73 BWPD, 310# TP, 475# CP, 30/64" chk. FINAL REPORT.

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.


	5. Lease Designation and Serial Number: U-01194
	6. If Indian, Allottee or Tribe Name: N/A
	7. Unit Agreement Name: Natural Buttes Unit
1. Type of Well: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER:	8. Well Name and Number: NBU #132
2. Name of Operator: Coastal Oil & Gas Corporation	9. API Well Number: 43-047-31938
3. Address and Telephone Number: P.O. Box 749, Denver, CO 80201-0749 (303) 573-4476	10. Field and Pool, or Wildcat: Natural Buttes
4. Location of Well Footages: 594' FNL & 850' FWL County: Uintah QQ, Sec., T., R., M.: NWNW Section 26-T9S-R21E State: Utah	

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT (Submit In Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input type="checkbox"/> Multiple Completion <input checked="" type="checkbox"/> Other Lower tbg, omstall PLE	<input type="checkbox"/> Abandon * <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input type="checkbox"/> Other
<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recompletion <input type="checkbox"/> Perforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Perforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off
Approximate date work will start _____ Upon approval. _____	Date of work completion _____ Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form. * Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please see the attached procedure for work to be completed in the subject well.



13. Name & Signature: Bonnie Carson Title Senior Environmental Analyst Date 01/28/97
Bonnie Carson

(This space for State use only)

**Accepted by the
Utah Division of
Oil, Gas and Mining**

FOR RECORD ONLY
(See Instructions on Reverse Side)

2/10/97

NBU #132-26-9-21
NATURAL BUTTES FIELD
SECTION 26 T9S R21E
WORKOVER PROCEDURE #w.u

WELL DATA

LOCATION: 594' FNL 850' FWL SEC. 26 T9S R21E
ELEVATION: 4065' GR., 4971' KB.
TD: 6377', PBD 6368' (6/91)
CSG: 8-5/8", 24.0#, K-55 @ 270' w/ 180 SX.
5-1/2", 17.0#, J-55 @ 6376' w/ 745 SX.
CMT ANNULUS w/ 280 SX.
TBG: 2-3/8", 4.7#, J-55 @ 5660' (1994)
COIL TBG @ 6100' (1994)
FORMATION(S): WASATCH 5014' - 6332', 19 HOLES (1991)


PROCEDURE

1. MI & RU coil tubing unit. Kill 1-1/4" tbg w/ 3% KCL water. POOH & spool 1-1/4" CT. RD CTU.
2. MI & RU pulling unit. Blow down & kill well. ND WH. NU BOP.
3. RIH w/ 2-3/8" tbg & land tbg @ 6293'. BP @ 6332'.
4. ND BOP. NU WH. RD & MO pulling unit.
5. Install PLE. Swab / flow well to clean up. Return the well to sales.

NBU #132-26-9-21
 NATURAL BUTTES FIELD
 SECTION 26 T9S R21E

WELL DATA

LOCATION: 594' FNL 850' FWL SEC. 26 T9S R21E
 ELEVATION: 4065' GR., 4971' KB.
 TD: 6377', PBTD 6368' (6/91)
 CSG: 8-5/8", 24.0#, K-55 @ 270' w/ 180 SX.
 5-1/2", 17.0#, J-55 @ 6376' w/ 745 SX.
 TBG: 2-3/8", 4.7#, J-55 @ 5660' (1994)
 COIL TBG @ 6100' (1994)
 FORMATION(S): WASATCH 5014' - 6332', 19 HOLES (1994)



2 3/8" 4.7# @ 5660'
 1 1/2" coil TBG @ 6100'

8 5/8" @
 270'

WASATCH
 4876'

- 5019, 5018
- 5060, 5061, 5061
- 5448
- 5476
- 5740, 5744, 5749
- 5888, 5892, 5902
- 6040
- 6188, 6195
- 6227
- 6293
- 6332

(10/99) Lwr 2 3/8" tbg to 5660'. Installed CT @ 6100'
 IPF 349 MCF + 0.75 BWPD 3/4" CK FTP 310# 475# CP

(11/91) WASATCH 5014'-6332' - 11 ZONES 19 holes
 FRAC (LJSPF) w/ 4' C.C.
 5014' 5060' 5748' 5476' 5740' 5888' 6040' 6188' 6227' 6293' 6332'
 5018' 5064' 5744' 5892' 6195'
 5069' 5744' 5902'


BD w/ 4000 gal 3% KCL water IPF 500 MCF 2 3/4" CK FTP 195#

FRAC w/ 352,000# sand + 195,000 gal gel w/ 30% CaZ

(11/91) IPF 3200 MCF 2 3/4" CK FTP 1900# CP 1100#

1/2" @
 6376

TD 6377'



DRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER:		5. Lease Designation and Serial Number: U-01194
2. Name of Operator: Coastal Oil & Gas Corporation		6. If Indian, Allottee or Tribe Name: N/A
3. Address and Telephone Number: P.O. Box 749, Denver, CO 80201-0749 (303) 573-4476		7. Unit Agreement Name: Natural Buttes Unit
4. Location of Well Footages: 594' FNL & 850' FWL County: Uintah QQ, Sec., T., R., M.: NWNW Section 26-T9S-R21E State: Utah		8. Well Name and Number: NBU #132
		9. API Well Number: 43-047-31938
		10. Field and Pool, or Wildcat: Natural Buttes

11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon	<input type="checkbox"/> Abandon *
<input type="checkbox"/> Repair Casing	<input type="checkbox"/> Repair Casing
<input type="checkbox"/> Change of Plans	<input type="checkbox"/> Change of Plans
<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Convert to Injection
<input type="checkbox"/> Fracture Treat or Acidize	<input type="checkbox"/> Fracture Treat or Acidize
<input type="checkbox"/> Multiple Completion	<input type="checkbox"/> Other CO, lower tbg, install PLE
<input type="checkbox"/> Other	
<input type="checkbox"/> New Construction	<input type="checkbox"/> New Construction
<input type="checkbox"/> Pull or Alter Casing	<input type="checkbox"/> Pull or Alter Casing
<input type="checkbox"/> Recompletion	<input type="checkbox"/> Perforate
<input type="checkbox"/> Perforate	<input type="checkbox"/> Vent or Flare
<input type="checkbox"/> Vent or Flare	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Water Shut-Off	

Date of work completion 5/14/97

Report results of **Multiple Completions** and **Recompletions** to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

Approximate date work will start _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please see the attached chronological history for work completed in the subject well.

13. Name & Signature: Bonnie Carson Title Senior Environmental Analyst Date 05/23/97

(This space for State use only)

- 05/12/97 **RIH w/tbg, CO PBTD.** RDMO CIGE #178 & road rig to NBU #132. MIRU. SICP 300 psi, SITP 300 psi. RU pmp & lines & pmp 10 bbls dn tbg. ND WH & NU BOPs w/hydril & SH. RU floor & tbg equip. PU & LD hanger & blast jt. Talley & PU - RIH w/tbg, tag 6240'. POOH 10 stds from perf, EOT @ 5660' & SDFN @ 1:30 PM.
DC: \$3,609 TC: \$3,609
- 05/13/97 **RIH w/tbg & tag fill.** SICP 400 psi, SITP 450 psi. Blow well dn. Pmp 10 bbls dn tbg. RIH w/tbg to 6240'. RU swivel & b/circ w/air foam. CO from 6240' to 6368' PBTD & circ hole clean. RD swivel & POOH to float. Pmp 10 bbls dn tbg. POOH w/tbg from perf, EOT 5660' & SDFN @ 5 PM.
DC: \$6,324 TC: \$9,933
- 05/14/97 **Well on production.** SICP 450 psi, SITP 450 psi. Blow well dn, pmp 10 bbls dn tbg. RIH w/tbg & tag @ 6354'. LD 3 jts. PU hanger & land tbg w/20 jts 2 $\frac{3}{8}$ " tbg & 617.34' to well, EOT @ 6277' & SN @ 6245'. ND BOPs w/hydril & SH & NU WH. RDMO @ 10:30 AM. MIRU Delsco & swab, IFL 4300'. Made 7 runs, rec 28 BW, FFL 5200', SICP 350 psi, SITP 150 psi. Put well on prod @ 3:30 PM. Flowing 132 MCF, 1 BW, 135 TP, 320 CP, on 24/64" chk.
DC: \$8,489 TC: \$18,422
- 05/15/97 Flowing 477 MCF, 2 BW, 125 TP, 250 CP, on 30/64" chk.
- 05/16/97 Flowing 488 MCF, 1 BW, 110 TP, 273 CP, on 30/64" chk.
- 05/17/97 Flowing 451 MCF, 0 BW, 120 TP, 304 CP, on 30/64" chk.
- 05/18/97 Flowing 348 MCF, 0 BW, 130 TP, 297 CP, on 30/64" chk. **Final Report**

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT" - for such proposals

5. Lease Designation and Serial No.

See Attached Spreadsheet

6. If Indian, Alottee or Tribe Name

See Attached Spreadsheet

7. If Unit or CA, Agreement Designation

Natural Buttes Unit

8. Well Name and No.

See Attached Spreadsheet

9. API Well No.

See Attached Spreadsheet

10. Field and Pool, Or Exploratory Area

Natural Buttes

11. County or Parish, State

Utah County, Utah

SUBMIT IN TRIPLICATE

1. Type of Well

Oil Well Gas Well Other

2. Name of Operator

Coastal Oil & Gas Corporation

3. Address and Telephone No.

P. O. Box 749, Denver, CO 80201-0749

(303) 573-4476

4. Location of Well (Footage, Sec., T., R., M., Or Survey Description)

See Attached Spreadsheet

43-047-31938

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

Notice of Intent
 Subsequent Report
 Final Abandonment Notice


TYPE OF ACTION

Abandonment
 Recompletion
 Plugging Back
 Casing Repair
 Altering Casing
 Other Dispose of Produced Water
 Change of Plans
 New Construction
 Non-Routine Fracturing
 Water Shut-Off
 Conversion to Injection
 Dispose Water

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markets and zones pertinent to this work.)

The Operator requests permission to dispose produced water from the referenced wells into storage tanks on the individual locations. The water will subsequently be hauled by truck to Coastal's NBU #159 salt water disposal well located at NESW, Section 35, T9S-R21E, where the produced water will be injected.



14. I hereby certify that the foregoing is true and correct

Signed Bonnie Carson Title Senior Environmental Analyst Date 07/07/97
Bonnie Carson

(This space for Federal or State office use)

APPROVED BY _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

COASTAL OIL & GAS CORPORATION
Attached hereto Sundry Notices and Reports on Wells dated July 7, 1997

Well Name & No.	API No.	Lease Designation & Serial Number	If Indian, Allottee or Tribe Name	Footages	Qtr/Qtr	Section	Township	Range	Field	County
CIGE #113D-21-9-21	43-047-31944	UTU-0576	Ute	2082' FNL & 1849' FEL	SW/NE	21	9S	21E	Natural Buttes	Uintah
CIGE #123-7-9-21	43-047-32047	UTU-0575B	N/A	1980' FNL & 1980' FEL	SW/NE	7	9S	21E	Natural Buttes	Uintah
CIGE #155-9-21	43-047-32157	UTU-011888	N/A	1613' FNL & 766' FEL	SE/NE	9	9S	21E	Natural Buttes	Uintah
CIGE #46-21-9-21	43-047-30529	U-0576	Ute	1019' FNL & 778' FEL	NE/NE	21	9S	21E	Natural Buttes	Uintah
CIGE #70-20-9-21	43-047-30636	U-0575	Ute	1894' FSL & 804' FEL	NE/SE	20	9S	21E	Natural Buttes	Uintah
CIGE #72-18-9-21	43-47-30634	U-0575	Ute	2049' FNL & 2291' FEL		18	9S	21E	Natural Buttes	Uintah
CIGE #90D-9-9-21J	43-047-31149	U-01188-B	Ute	774' FNL & 1942' FEL		9	9S	21E	Natural Buttes	Uintah
CIGE #91D-15-9-21J	43-47-31151	U-01188	Ute	630' FNL & 1652' FEL	NW/NE	15	9S	21E	Natural Buttes	Uintah
NBU #103	43-047-31956	UTU-0141315	Ute	2026' FNL & 1932' FWL	SE/NW	10	9S	21E	Natural Buttes	Uintah
NBU #111	43-47-31920	U-01194-ST	N/A	1982' FNL & 785' FWL	SW/NW	25	9S	21E	Natural Buttes	Uintah
NBU #120	43-047-31972	UTU-0141315	Ute	891' FNL & 532' FWL	NW/NW	10	9S	21E	Natural Buttes	Uintah
NBU #132	43-047-31938	U-01194	N/A	594' FNL & 850' FWL	NWNW	26	9S	21E	Natural Buttes	Uintah
NBU #142	43-047-32013	UTU-025187	N/A	1652' FSL & 1034' FEL	NE/SE	10	10S	22E	Natural Buttes	Uintah
NBU #143	43-047-32297	U-0141315	Ute	1752' FNL & 1713' FEL	NW/NE	10	9S	21E	Natural Buttes	Uintah
NBU #15	43-047-30204	ML-10170-01	N/A	1805' FWL & 601' FSL		26	9S	21E	Natural Buttes	Uintah
NBU #174	43-47-32193	U-0141315	N/A	454' FNL & 1154' FWL	NW/NW	11	9S	21E	Natural Buttes	Uintah
NBU #20	43-047-30250	U-0576	N/A	1330' FSL & 1330' FWL	SW	28	9S	21E	Natural Buttes	Uintah
NBU #205	43-047-32795	ML-23612	N/A	2110' FNL & 2607' FEL	SW/NE	1	10S	21E	Natural Buttes	Uintah
NBU #213	43-047-32401	U-025187	N/A	908' FNL & 1159' FWL	NW/NW	15	10S	22E	Natural Buttes	Uintah
NBU #217	43-047-32480	U-0576	Ute	1978' FSL & 2296' FWL	NE SW	28	9S	21E	Natural Buttes	Uintah
NBU #26	43-047-30252	U-01194-A-ST	N/A	1320' FSL & 1320' FEL		27	9S	21E	Natural Buttes	Uintah
NBU #31	43-047-30307	U-01197-A	N/A	1640' FWL & 1221' FSL	SW/SW	11	10S	22E	Natural Buttes	Uintah
NBU #39	43-047-30861	U-0132568A	N/A	1019' FWL & 956' FSL	SW/SW	29	10S	22E	Natural Buttes	Uintah
NBU #4	43-047-30056	U-0149075	N/A	757' FEL & 1399' FSL		23	9S	21E	Natural Buttes	Uintah
NBU #99	43-47-31745	U01194-ST	N/A	660' FSL & 660' FWL	SW/SW	25	9S	21E	Natural Buttes	Uintah

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depths, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL GAS WELL OTHER _____

2. NAME OF OPERATOR:
El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR: 8 South 1200 East CITY Vernal STATE Utah ZIP 84078 PHONE NUMBER: 435-789-4433

4. LOCATION OF WELL

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

FOOTAGES AT SURFACE:

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Name Change</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.

See Exhibit "A"

Bond # 400JU0708


Coastal Oil & Gas Corporation

NAME (PLEASE PRINT) John T. Elzner TITLE Vice President

SIGNATURE  DATE 06-15-01

El Paso Production Oil & Gas Company

NAME (PLEASE PRINT) John T. Elzner TITLE Vice President

SIGNATURE  DATE 06-15-01

(This space for State use only)

RECEIVED

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING

State of Delaware
Office of the Secretary of State

PAGE 1

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

MAR 11 2001

DIVISION OF
OIL, GAS AND MINING



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

0610204 8100

AUTHENTICATION: 1061007

010162788

DATE: 04-03-01

CERTIFICATE OF AMENDMENT

OF

CERTIFICATE OF INCORPORATION

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST." so that, as amended, said Article shall be and read as follows:

"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL & GAS CORPORATION

David L. Siddall
Vice President

Attest:

Margaret E. Roark
Margaret E. Roark, Assistant Secretary

RECEIVED

STATE OF DELAWARE
SECRETARY OF STATE
DIVISION OF CORPORATIONS
FILED 11:00 AM 03/09/2001
010118394 - 0610204

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

RECEIVED

JUL 12 2001

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:
3106
UTSL-065841
(UT-924)

JUL 10 2001

NOTICE

El Paso Production Oil & Gas Company : Oil and Gas
Nine Greenway Plaza :
Houston TX 77046-0095 :

Name Change Recognized


Acceptable evidence has been received in this office concerning the name change of Coastal Oil & Gas Corporation into El Paso Production Oil & Gas Company with El Paso Production Oil & Gas Company being the surviving entity.

For our purposes, the name change is recognized effective March 9, 2001.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Coastal Oil & Gas Corporation to El Paso Production Oil & Gas Company. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Wyoming and Colorado.



Opolonia L. Abeyta
Acting Chief, Branch of
Minerals Adjudication

Enclosure

1. Exhibit of Leases (1 pp)

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

Exhibit of Leases

UTUSL-065841A	UTU-47172	UTU-74415	UTU-53860
UTU-28652	UTU-50687	UTU-74416	UTU-66401
UTU-37943	UTU-52298	UTU-75091	UTU-67868
UTU-44089	UTU-0109054	UTU-75096	UTU-65389
UTU-44090A	UTU-0143511	UTU-75097	UTU-77084
UTU-61263	UTU-0143512	UTU-75673	UTU-61430
UTU-00343	UTU-38401	UTU-76259	UTU-72633
UTU-02651	UTU-38411	UTU-76260	UTU-72650
UTU-02651B	UTU-38418	UTU-76261	UTU-49692
UTU-0142175	UTU-38419	UTU-76493	UTU-57894
UTU-70235	UTU-38420	UTU-76495	UTU-76829
UTU-70406	UTU-38421	UTU-76503	UTU-76830
UTU-74954	UTU-38423	UTU-78228	UTU-76831
UTU-75132	UTU-38424	UTU-78714	
UTU-75699	UTU-38425	UTU-78727	
UTU-76242	UTU-38426	UTU-78734	
UTU-78032	UTU-38427	UTU-79012	
UTU-4377	UTU-38428	UTU-79011	
UTU-4378	UTU-53861	UTU-71694	
UTU-7386	UTU-58097	UTU-00576	
UTU-8344A	UTU-64376	UTU-00647	
UTU-8345	UTU-65222	UTU-01470D	
UTU-8347	UTU-65223	UTU-0136484	
UTU-8621	UTU-66746	UTU-8344	
UTU-14646	UTU-67178	UTU-8346	
UTU-15855	UTU-67549	UTU-8648	
UTU-25880	UTU-72028	UTU-28212	
UTU-28213	UTU-72632	UTU-30289	
UTU-29535	UTU-73009	UTU-31260	
UTU-29797	UTU-73010	UTU-33433	
UTU-31736	UTU-73013	UTU-34711	
UTU-34350	UTU-73175	UTU-46699	
UTU-34705	UTU-73434	UTU-78852	
UTU-37116	UTU-73435	UTU-78853	
UTU-37355	UTU-73444	UTU-78854	
UTU-37573	UTU-73450	UTU-075939	
UTU-38261	UTU-73900	UTU-0149767	
UTU-39223	UTU-74409	UTU-2078	
UTU-40729	UTU-74410	UTU-44426	
UTU-40736	UTU-74413	UTU-49530	
UTU-42469	UTU-74414	UTU-51026	

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH		4-KAS
2. CDW	<input checked="" type="checkbox"/>	5-LP <input checked="" type="checkbox"/>
3. JLT		6-FILE

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

X Merger

The operator of the well(s) listed below has changed, effective: **3-09-2001**

FROM: (Old Operator):
COASTAL OIL & GAS CORPORATION
Address: 9 GREENWAY PLAZA STE 2721
HOUSTON, TX 77046-0995
Phone: 1-(713)-418-4635
Account N0230

TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY
Address: 9 GREENWAY PLAZA STE 2721 RM 2975B
HOUSTON, TX 77046-0995
Phone: 1-(832)-676-4721
Account N1845

CA No.

Unit: NATURAL BUTTES

WELL(S)

NAME	API NO	ENTITY NO	SEC TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 6	43-047-30083	2900	24-09S-21E	FEDERAL	GW	P
NBU 210-24	43-047-31153	2900	24-09S-21E	FEDERAL	GW	P
NBU 219-24	43-047-31308	2900	24-09S-21E	FEDERAL	GW	P
NBU 301-24E	43-047-32131	2900	24-09S-21E	FEDERAL	GW	P
NBU 336-24E	43-047-32264	2900	24-09S-21E	FEDERAL	GW	P
NBU 386-24E	43-047-33056	2900	24-09S-21E	FEDERAL	GW	P
NBU 111	43-047-31920	2900	25-09S-21E	FEDERAL	GW	P
NBU 320	43-047-33201	99999	25-09S-21E	STATE	GW	APD
NBU 15	43-047-30204	2900	26-09S-21E	FEDERAL	GW	P
NBU 107	43-047-31916	2900	26-09S-21E	FEDERAL	GW	P
NBU 132	43-047-31938	2900	26-09S-21E	FEDERAL	GW	P
NBU 190	43-047-32232	2900	26-09S-21E	FEDERAL	GW	P
NBU 109	43-047-31917	2900	27-09S-21E	FEDERAL	GW	P
NBU 20	43-047-30250	2900	28-09S-21E	FEDERAL	GW	P
NBU 56	43-047-30884	2900	28-09S-21E	FEDERAL	GW	P
NBU 110	43-047-31924	2900	28-09S-21E	FEDERAL	GW	P
NBU 133	43-047-31950	2900	28-09S-21E	FEDERAL	GW	P
NBU 134	43-047-32011	2900	28-09S-21E	FEDERAL	GW	P
NBU 166	43-047-32065	2900	28-09S-21E	FEDERAL	GW	P
NBU 175	43-047-32143	2900	28-09S-21E	FEDERAL	GW	P

OPERATOR CHANGES DOCUMENTATION

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/19/2001
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/19/2001
- The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 06/21/2001
- Is the new operator registered in the State of Utah: YES Business Number: 608186-0143

5. If **NO**, the operator was contacted contacted on: N/A
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 07/10/2001
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 07/10/2001
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: 07/10/2001
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 07/31/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 07/31/2001
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE BOND VERIFICATION:

1. State well(s) covered by Bond No.: N/A

FEDERAL BOND VERIFICATION:

1. Federal well(s) covered by Bond No.: WY 2793

FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond No: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

FILMING:

1. All attachments to this form have been **MICROFILMED** on: _____

FILING:

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filed in each well file on: _____

COMMENTS: Master list of all wells involved in operator change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company shall be retained in the "Operator Change File".



United States Department of the Interior **RECEIVED**

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:

3106

UTU-25566 et al

(UT-924)

FEB 21 2002

NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas
410 Seventeenth Street, #2300 :
Denver Colorado 80215-7093 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405
UTU-20895
UTU-25566
UTU-43156
UTU-49518
UTU-49519
UTU-49522
UTU-49523



Robert Lopez
Chief, Branch of
Minerals Adjudication

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)



United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Washington, D.C. 20240

FEB 1 0 2003

IN REPLY REFER TO:
Real Estate Services

Carroll A. Wilson
Principal Landman
Westport Oil and Gas Company, L.P.
1368 South 1200 East
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

Director, Office of Trust Responsibilities

ACTING

Enclosure

memorandum

Branch of Real Estate Services
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.

We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.

CC: Minerals & Mining Section of RES
Ute Energy & Mineral Resources Department: Executive Director
chrono



JAN. 17. 2003 3:34PM

WESTPORT

NO. 173

P. 2

**WESTPORT OIL AND GAS COMPANY, L.P.**

410 Seventeenth Street #2300 Denver Colorado 80202-4436
Telephone: 303 573 5404 Fax: 303 573 5609

February 1, 2002

Department of the Interior
Bureau of Land Management
2850 Youngfield Street
Lakewood, CO 80215-7093
Attention: Ms. Martha Maxwell

RE: BLM Bond CO-1203
BLM Nationwide Bond 158626364
Surety - Continental Casualty Company
Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.
Assumption Rider - Westport Oil and Gas Company, L.P.

Dear Ms. Maxwell:

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,
Westport Oil and Gas Company, L.P.

Debby J. Black
Debby J. Black
Engineer Technician

Encl:



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

IN REPLY REFER TO
UT-922

February 27, 2003

Westport Oil and Gas Company, L.P.
Attn: Gary D. Williamson
1670 Broadway, Suite 2800
Denver, Colorado 80202

Re: Natural Buttes Unit
Uintah County, Utah

Gentlemen:

On February 27, 2003, we received an indenture dated December 17, 2002, whereby El Paso Production Oil & Gas Company resigned as Unit Operator and Westport Oil and Gas Company, L.P., was designated as Successor Unit Operator for the Natural Buttes Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective February 27, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Natural Buttes Unit Agreement.

Your nationwide (Colorado) oil and gas bond No. 1203 will be used to cover all operations within the Natural Buttes Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)
SITLA
Division of Oil, Gas & Mining
Minerals Adjudication Group
File - Natural Buttes Unit (w/enclosure)
Agr. Sec. Chron
Fluid Chron

UT922:TAThompson:tt:02/27/2003

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 9 Greenway Plaza CITY Houston STATE TX ZIP 77064-0995 PHONE NUMBER: (832) 676-5933		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		8. WELL NAME and NUMBER: Exhibit "A"
		9. API NUMBER:
		10. FIELD AND POOL, OR WILDCAT: COUNTY: STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND # _____
State Surety Bond No. RLB0005236
Fee Bond No. RLB0005238

EL PASO PRODUCTION OIL & GAS COMPANY

By: 
Jon R. Nelsen, Attorney-in-Fact

RECEIVED
FEB 28 2003
DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) WESTPORT OIL AND GAS COMPANY, L.P. David R. Dix	TITLE Agent and Attorney-in-Fact
SIGNATURE 	DATE 12/17/02

(This space for State use only)

Form 3160-3
(August 1999)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or reenter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
WESTPORT OIL & GAS COMPANY, L.P.

3a. Address
P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SEE ATTACHED EXHIBIT "A"

5. Lease Serial No.
SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
SEE ATTACHED EXHIBIT "A"

9. API Well No.
SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State
UINTAH COUNTY, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal
			<input type="checkbox"/> Water Shut-Off
			<input type="checkbox"/> Well Integrity
			<input checked="" type="checkbox"/> Other
			SUCCESSOR OF OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed if testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF, BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Signature

Date

March 4, 2003

BUREAU OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 03/12/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 03/12/2003

3. Bond information entered in RBDMS on: N/A

4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: RLB 0005236

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 158626364

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: RLB 0005239

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB 0005238

2. The **FORMER** operator has requested a release of liability from their bond on: N/A

The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
Multiple Wells - see attached

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.
891008900A

8. Well Name and No.
Multiple Wells - see attached

9. API Well No.
Multiple Wells - see attached

10. Field and Pool, or Exploratory Area
Natural Buttes Unit

11. County or Parish, State
Uintah County, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
WESTPORT OIL & GAS COMPANY, L.P.

3a. Address
P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Multiple Wells - see attached
9S 21E 26 4304731938

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Westport Oil & Gas requests a variance to Onshore Order No. 4, Part IIIC.a. requiring each sales tank be equipped with a pressure-vacuum thief hatch and/or vent line valve. The variance is requested as an economic analysis shows the value of the shrunk condensate will not payout the incremental cost of purchasing and maintaining the valve resulting in a loss of value over the producing life of the well.

The volume lost to shrinkage by dropping the tank pressure from 6 ozs. to 0 psig is shown to be 0.3% of the tank volume. This was determined by lab analysis of a representative sample from the field. The sample shrunk from 98.82% of original volume to 98.52% when the pressure was dropped. The average NBU well produces approximately 6 bbls condensate per month. The resulting shrinkage would amount to 0.56 bbls per month lost volume due to shrinkage. The value of the shrunk and lost condensate does not recoup or payout the cost of installing and maintaining the valves and other devices that hold the positive tank pressure. An economic run based on the loss and costs is attached.

Westport Oil & gas requests approval of this variance in order to increase the value of the well to the operator and the mineral royalty owners.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) J.T. Conley Title Operations Manager Date: 9-2-2003

Signature *J.T. Conley* Initials: JTC Date: 9-2-2003

SEP 10 2003
DIV. OF OIL & GAS

THIS SPACE FOR FEDERAL OR STATE USE

Approved by _____ Title _____ Date _____

Office Oil, Gas and Mining Date: 9/16/03

Federal Approval of This Action Is Necessary

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Westport Oil & Gas, L.P.

Project Economics Worksheet

Instructions: Fill in blue boxes with before and after project data. The evaluation results are shown below and graphed automatically at the bottom of the page. This sheet is protected to prevent accidental alteration of the formulas. See JTC for changes. OPX entered as annual costs and/or as unit OPX costs for \$/BF and \$/MCF

Project Name: **Condensate Shrinkage Economics**

Is this job a well pull or production rig job ??? N (Y or N)

	BEFORE \$/Year	AFTER \$/Year	DIFFERENCE \$/Year
Gross Oil Revenue	\$1,088	\$1,099	\$11
Gross Gas Revenue	\$0	\$0	\$0
NGL Revenue	\$0	\$0	\$0
PULING UNIT SERVICE			\$0
WIRELINE SERVICE			\$0
SUBSURF EQUIP REPAIRS			\$0
COMPANY LABOR			\$0
CONTRACT LABOR	\$0	\$200	\$200
CONTR SERVICE			\$0
LEASE FUEL GAS	\$0	\$0	\$0
UTILITIES - ELECTRICITY	\$0	\$0	\$0
CHEMICAL TREATING			\$0
MATERIAL & SUPPLY	\$0	\$150	\$150
WATER & HAULING			\$0
ADMINISTRATIVE COSTS			\$0
GAS PLANT PROCESSING			\$0
Totals	\$0	\$350	\$350

Increased OPX Per Year

Investment Breakdown:

	Cap/Exp Code	Cost, \$
Capital \$	820/830/840	\$1,200
Expense \$	830/860	\$0
Total \$		\$1,200

Oil Price	\$ 23.00	\$/BO
Gas Price	\$ 3.10	\$/MCF
Electric Cost	\$ -	\$/ HP / day
OPX/BF	\$ 2.00	\$/BF
OPX/MCF	\$ 0.62	\$/MCF

Production & OPX Detail:

	Before	After	Difference
Oil Production	0.192 BOPD	0.194 BOPD	0.002 BOPD
Gas Production	0 MCFPD	0 MCFPD	0 MCFPD
Wtr Production	0 BWPD	0 BWPD	0 BWPD
Horse Power	HP	HP	0 HP
Fuel Gas Burned	MCFPD	MCFPD	0 MCFPD

Project Life:

Life = Years
(Life no longer than 20 years)

Internal Rate of Return:

After Tax IROR =

AT Cum Cashflow:

Operating Cashflow = (Discounted @ 10%)

Payout Calculation:

$$\text{Payout} = \frac{\text{Total Investment}}{\text{Sum(OPX + Incremental Revenue)}} = 1$$

Payout occurs when total AT cashflow equals investment
See graph below, note years when cashflow reaches zero

Payout = Years or Days


Gross Reserves:

Oil Reserves = 6 BO
Gas Reserves = 0 MCF
Gas Equiv Reserves = 38 MCFE

Notes/Assumptions:

An average NBW well produces 0.192 Bcpd with no tank pressure. The production is increased to 0.194 Bcpd if 4 qzs of pressure are placed on the tank. The increased production does not payout the valve cost or the estimated annual maintenance costs.

Project: Condensate Shrinkage Economics



Westport Oil and Gas, Inc.

NBU/Ouray Field

RFL 2003-022

COMPARISON OF FLASH BACK PRESSURES

Calculated by Characterized Equation-of-State

Flash Conditions		Gas/Oil Ratio (scf/STbbl) (A)	Specific Gravity of Flashed Gas (Air=1.000)	Separator Volume Factor (B)	Separator Volume Percent (C)
psig	°F				

Calculated at Laboratory Flash Conditions

80	70			1.019	
0	122	30.4	0.993	1.033	101.37%
0	60	0.0	—	1.000	98.14%

Calculated Flash with Backpressure using Tuned EOS

80	70			1.015	
6.0 oz	65	24.6	0.777	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
4.0 oz	65	24.7	0.778	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
2.0 oz	65	24.7	0.779	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
0	65	24.8	0.780	1.003	98.82%
0	60	0.0	—	1.000	98.52%

(A) Cubic Feet of gas at 14.696 psia and 60 °F per Barrel of Stock Tank Oil at 60 °F.

(B) Barrels of oil at indicated pressure and temperature per Barrel of Stock Tank Oil at 60 °F.

(C) Oil volume at indicated pressure and temperature as a percentage of original saturated oil volume.

Note: Bubblepoint of sample in original sample container was 80 psig at 70° F with 1 cc water

WELL	LEGALS	STFLEASENO	CANUMBER	APINO
NBU 058N2	27-10-22 NENW	UTU473	891008900A	430473083800S1
NBU 060	26-9-21 NWSW	U01194	891008900A	430473172800S1 ✓
NBU 062N3	16-10-21 SENW	ML10755	891008900A	430473090900S1
NBU 063N3	12-9-21 SWNW	UTU0141317	891008900A	430473109700S1
NBU 064N3	8-9-21 NESE	UTU0575B	891008900A	430473109800S1
NBU 065N3	14-9-21 SESW	UTU01193	891008900A	430473109900S1
NBU 067A	4-10-22 SWNE	UTU01191	891008900A	430473173700S1
NBU 068N2	26-9-21 NESE	ML22934	891008900A	430473108900S1 ✓
NBU 069N2	35-9-21 SWSW	U01194	891008900A	430473109000S1 ✓
NBU 070N3	3-10-22 SWNW	UTU01191	891008900A	430473110000S1
NBU 072N3	12-10-20 NWNW	UTU4478	891008900A	430473108800S1
NBU 074N3	24-10-20 SWNE	ML22790	891008900A	430473108700S1
NBU 075N3	20-10-21 NENE	UTU02278	891008900A	430473110300S1
NBU 078	30-9-22 NWNW	U463	891008900A	430473176200S1
NBU 080V	34-9-22 NWSW	UTU0149077	891008900A	430473124000S1
NBU 081V	35-9-21 SWNW	U01194	891008900A	430473123200S1 ✓
NBU 083J	27-9-21 NESW	U01194A	891008900A	430473123500S1 ✓
NBU 084V	6-10-22 NWNE	UTU01195B	891008900A	430473124500S1
NBU 085J	4-10-22 SWNW	UTU01191A	891008900A	430473124600S1
NBU 086J	3-10-22 NENE	UTU01191A	891008900A	430473125100S1
NBU 087J	3-10-22 NESW	UTU01191	891008900A	430473125000S1
NBU 088V	26-9-21 NENE	U01194	891008900A	430473123300S1 ✓
NBU 093	33-9-22 NESE	UTU01191A	891008900A	430473175300S1
NBU 097	25-9-21 NENW	U01189	891008900A	430473174400S1 ✓
NBU 098V	34-9-21 SWSW	U01194A	891008900A	430473132700S1 ✓
NBU 099	25-9-21 SWSW	U01194	891008900A	430473174500S1 ✓
NBU 101	3-10-21 NWSE	UTU0149078	891008900A	430473175500S1
NBU 102	5-10-21 SESW	UTU01393D	891008900A	430473175700S1
NBU 1021-16G	16-10-21 SWNE	ML10755	891008900A	430473511100S1 ✓
NBU 1021-20	2-10-21 SWSE	ML13826	891008900A	430473511000S1 ✓
NBU 103	10-9-21 SENW	U0141315	891008900A	430473195600S1
NBU 104	16-9-21 SENE	ML3282	891008900A	430473195700S1
NBU 105	17-9-21 SWSW	UTU0575	891008900A	430473230200S1
NBU 106	21-9-21 NESW	UTU0576	891008900A	430473194600S1
NBU 107	26-9-21 SENW	U01194	891008900A	430473191600S1
NBU 108	19-9-22 SESE	UTU0284	891008900A	430473195800S1
NBU 109	27-9-21 SENE	U01194A	891008900A	430473191700S1 ✓
NBU 110	28-9-21 NENE	U05676	891008900A	430473192400S1
NBU 111	25-9-21 SWNW	U01194	891008900A	430473192000S1 ✓
NBU 112	33-9-22 SESE	UTU01191	891008900A	430473193000S1
NBU 113	34-9-22 SESE	UTU0149077	891008900A	430473193100S1
NBU 114	5-10-21 SWSW	UTU01393D	891008900A	430473192300S1
NBU 115	10-10-21 NENW	UTU0149079	891008900A	430473192900S1
NBU 116	6-10-22 NWNW	UTU464	891008900A	430473192500S1
NBU 117	10-10-22 NENE	U01197A	891008900A	430473191400S1
NBU 118	22-9-20 SENE	UTU0577B	891008900A	430473196900S1
NBU 119	22-9-20 SENW	UTU0577B	891008900A	430473197300S1
NBU 120	10-9-21 NWNW	U0141315	891008900A	430473197200S1
NBU 121	13-9-21 NWNE	U01193	891008900A	430473208600S1
NBU 122	13-9-21 SESE	U01193	891008900A	430473230300S1
NBU 123	15-9-21 NWNW	UTU01188	891008900A	430473197400S1
NBU 124	16-9-21 NWNE	ML3282	891008900A	430473197100S1
NBU 125	17-9-21 SESE	UTU0575	891008900A	430473235000S1
NBU 126	21-9-21 SENW	UTU0576	891008900A	430473234900S1
NBU 127	21-9-21 SWNW	UTU0576	891008900A	430473196300S1
NBU 128	21-9-21 SWSW	UTU0576	891008900A	430473196400S1
NBU 129	22-9-21 SENE	UTU010950A	891008900A	430473196500S1
NBU 130	22-9-21 SWNW	UTU0147566	891008900A	430473196700S1
NBU 131	23-9-21 NWSW	UTU0149075	891008900A	430473196800S1
NBU 132	26-9-21 NWNW	U01194	891008900A	430473193800S1 ✓
NBU 133	28-9-21 SWNE	U05676	891008900A	430473195000S1
NBU 134	28-9-21 SWSW	U05676	891008900A	430473201100S1
NBU 136	19-9-22 SWSE	UTU0284	891008900A	430473196800S1
NBU 137	30-9-22 SESE	ML22935	891008900A	430473193900S1 ✓
NBU 138A	33-9-22 SENE	UTU01191A	891008900A	430473215100S1
NBU 139	14-10-21 SWNE	UTU465	891008900A	430473194800S1
NBU 140	5-10-22 NWNE	UTU01191A	891008900A	430473194700S1
NBU 141	6-10-22 SENW	UTU464	891008900A	430473201700S1
NBU 142	10-10-22 NESE	UTU025187	891008900A	430473201300S1
NBU 143	10-9-21 SWNE	U0141315	891008900A	430473229700S1
NBU 144	23-9-21 NWNW	UTU0149075	891008900A	430473204400S1
NBU 145	27-9-21 NWNE	U01194A	891008900A	430473197600S1 ✓
NBU 146	14-10-21 SWNW	UTU465	891008900A	430473198500S1
NBU 147	4-10-22 NWSW	UTU01191	891008900A	430473198400S1
NBU 148	4-10-22 SESW	UTU01191	891008900A	430473198300S1

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective: **1/6/2006**

FROM: (Old Operator): N2115-Westport Oil & Gas Co., LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024	TO: (New Operator): N2995-Kerr-McGee Oil & Gas Onshore, LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024
---	--

WELL NAME	CA No.	Unit:	NATURAL BUTTES UNIT					
	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- If **NO**, the operator was contacted on:
- (R649-9-2) Waste Management Plan has been received on: IN PLACE
- Inspections of LA PA state/fee well sites complete on: n/a 3 LA wells & all PA wells transferred
- Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet

7. Federal and Indian Units:
 The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006

8. Federal and Indian Communization Agreements ("CA"):
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

9. Underground Injection Control ("UIC") The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on:

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 5/15/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
- Bond information entered in RBDMS on: 5/15/2006
- Fee/State wells attached to bond in RBDMS on: 5/16/2006
- Injection Projects to new operator in RBDMS on: _____
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: CO1203
- Indian well(s) covered by Bond Number: RLB0005239
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
 The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
KERR-McGEE OIL & GAS ONSHORE LP

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SEE ATTACHED

5. Lease Serial No.
MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006. KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

*BLM BOND = C01203
BIA BOND = RLB0005239*

APPROVED 5/16/06

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) RANDY BAYNE	Title DRILLING MANAGER
Signature <i>Randy Bayne</i>	Date May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
 Oil Well Gas Well Other

2. Name of Operator
WESTPORT OIL & GAS COMPANY L.P.

3a. Address
1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)
(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SEE ATTACHED

5. Lease Serial No.
MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State
UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal
			<input type="checkbox"/> Water Shut-Off
			<input type="checkbox"/> Well Integrity
			<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06
Earlene Russell
 Division of Oil, Gas and Mining
 Earlene Russell, Engineering Technician

RECEIVED
 MAY 10 2006

DIV OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed) BRAD LANEY	Title ENGINEERING SPECIALIST
Signature <i>Brad Laney</i>	Date May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by <i>Brad Laney</i>	Title	Date 5-9-06
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Colorado State Office
2850 Youngfield Street
Lakewood, Colorado 80215-7076

IN REPLY REFER TO:

CO922 (MM)
3106
COC017387 et. al.

March 23, 2006

NOTICE

Kerr-McGee Oil & Gas Onshore L.P. :
1999 Broadway, Suite 3700 : Oil & Gas
Denver, CO 80202 :

Merger/Name Change - Recognized

On February 28, 2006 this office received acceptable evidence of the following mergers and name conversion:

Kerr-McGee Oil & Gas Onshore L.P., a Delaware Limited Partnership, and Kerr-McGee Oil & Gas Onshore LLC, a Delaware Limited Partnership merger with and into Westport Oil and Gas Company L.P., a Delaware Limited Partnership, and subsequent Westport Oil & Gas Company L.P. name conversion to Kerr-McGee Oil & Gas Onshore L.P.

For our purposes the merger and name conversion was effective January 4, 2006, the date the Secretary of State of Delaware authenticated the mergers and name conversion.

Kerr-McGee Oil & Gas Onshore L.P. provided a list of oil and gas leases held by the merging parties with the request that the Bureau of Land Management change all their lease records from the named entities to the new entity, Kerr-McGee Oil & Gas Onshore L.P. In response to this request each state is asked to retrieve their own list of leases in the names of these entities from the Bureau of Land Management's (BLM) automated LR2000 data base.

The oil and gas lease files identified on the list provided by Kerr-McGee Oil & Gas Onshore L.P. have been updated as to the merger and name conversion. We have not abstracted the lease files to determine if the entities affected by the acceptance of these documents holds an interest in the lease, nor have we attempt to identify leases where the entity is the operator on the ground that maintains vested record title or operating rights interests. If additional documentation, for change of operator, is required you will be contacted directly by the appropriate Field Office. The Mineral Management Services (MMS) and other applicable BLM offices were notified of the merger with a copy of this notice

Please contact this office if you identify additional leases where the merging party maintains an interest, under our jurisdiction, and we will document the case files with a copy of this notice. If the leases are under the jurisdiction of another State Office that information will be forwarded to them for their action.

Three riders accompanied the merger/name conversion documents which will add Kerr-McGee Oil and Gas Onshore LLC as a principal to the 3 Kerr-McGee bonds maintained by the Wyoming State Office. These riders will be forward to them for their acceptance.

The Nationwide Oil & Gas Continental Casualty Company Bond #158626364 (BLM Bond #CO1203), maintained by the Colorado State Office, will remain in full force and effect until an assumption rider is accepted by the Wyoming State Office that conditions their Nationwide Safeco bond to accept all outstanding liability on the oil and gas leases attached to the Colorado bond.

If you have questions about this action you may call me at 303.239.3768.

/s/Martha L. Maxwell
Martha L. Maxwell
Land Law Examiner
Fluid Minerals Adjudication

Attachment:

List of OG Leases to each of the following offices:

MMS MRM, MS 357B-1

WY, UT, NM/OK/TX, MT/ND, WY State Offices

CO Field Offices

Wyoming State Office

Rider #1 to Bond WY2357

Rider #2 to Bond WY1865

Rider #3 to Bond WY1127



United States Department of the Interior



BUREAU OF LAND MANAGEMENT
Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>

IN REPLY REFER TO:
3106
(UT-922)

March 27, 2006

Memorandum

To: Vernal Field Office

From: Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the merger recognized by the Bureau of Land Management, Colorado State Office. We have updated our records to reflect the merger from Westport Oil and Gas Company L.P. into Kerr-McGee Onshore Oil and Gas Company. The merger was approved effective January 4, 2006.

Chief, Branch of
Fluid Minerals

Enclosure

Approval letter from BLM COSO (2 pp)

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare
Dave Mascarenas
Susan Bauman

RECEIVED

MAR 28 2006

DIV. OF OIL, GAS & MINERALS

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UO1194ST
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 132
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.	9. API NUMBER: 43047319380000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6007 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0594 FNL 0850 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 26 Township: 09.0S Range: 21.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 2/5/2010	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input checked="" type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR REQUESTS AUTHORIZATION TO TEMPORARILY ABANDON THE SUBJECT WELL LOCATION. THE OPERATOR PROPOSES TO TEMPORARILY ABANDON THE WELL TO DRILL THE NBU 921-26D PAD WELLS, WHICH CONSIST OF NBU 921-26C3CS, NBU 921-26D3AS, NBU 921-26D3DS. PLEASE REFER TO THE ATTACHED TEMPORARILY ABANDON PROCEDURE.

Approved by the Utah Division of Oil, Gas and Mining

Date: February 03, 2010

By: *Derek Duff*

NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 2/2/2010	

NBU 132
 594' FNL & 850' FWL
 NWNW SEC.26, T9S, R21E
 Uintah County, UT

KBE: 4975'
 GLE: 4963'
 TD: 6377'
 PBDT: 6368'

API NUMBER: 43-047-31938
 LEASE NUMBER: U-01194
 WINS #: 72119
 WI: 100.00000%
 NRI: 81.494445%

CASING: 12 1/4" hole
 8 5/8" 24# K-55 @ 270' (GL)
 Cement w/ 180 sx Prem AG

7.875" hole
 5 1/2" 17# N-80 @ 6376'
 Cement w/ 745 sks Hi-Fill & 50/50 Poz
 TOC @ 1070' per CBL, but pumped top job on 6/16/91 (after CBL) w/ 38 sx, report states "Caught pressure. Squeezed to 700 psi. Cmt to surface." Effective TOC @ surface.

TUBING: 2 3/8" 4.7# J-55 tubing landed at 6277'

Tubular/Borehole	Drift inches	Collapse psi	Burst psi	Capacities		
				Gal./ft.	Cuft/ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1624	0.02173	0.0039
5.5" 17# J-55	4.892	4910	5320	0.9764	0.1305	0.02324
8.625" 24# J-55	7.972	1370	3930	2.6749	0.3537	0.0636
Annular Capacities						
2.375" tbg. X 5 1/2" 18# csg				0.7013	0.0937	0.0167
5.5" csg X 8 5/8" 24# csg				1.296	0.1733	0.0309
5.5" csg X 7.875 borehole				1.4407	0.1926	0.0343
8.625" csg X 12 1/4" borehole				3.0874	0.4127	0.0735

GEOLOGIC INFORMATION:

Formation Depth to top, ft.
 Uinta Surface
 Wasatch 4760'

Tech. Pub. #92 Base of USDW's

USDW Elevation 3800' MSL
 USDW Depth 1175' KBE

PERFORATIONS:

Formation	Date	Top	Spf	Status
Wasatch	Jun-91	5014	1	Open
Wasatch	Jun-91	5018	1	Open
Wasatch	Jun-91	5060	1	Open
Wasatch	Jun-91	5064	1	Open
Wasatch	Jun-91	5069	1	Open
Wasatch	Jun-91	5448	1	Open
Wasatch	Jun-91	5476	1	Open
Wasatch	Jun-91	5740	1	Open
Wasatch	Jun-91	5744	1	Open
Wasatch	Jun-91	5749	1	Open
Wasatch	Jun-91	5888	1	Open
Wasatch	Jun-91	5892	1	Open
Wasatch	Jun-91	5902	1	Open
Wasatch	Jun-91	6040	1	Open
Wasatch	Jun-91	6188	1	Open
Wasatch	Jun-91	6195	1	Open
Wasatch	Jun-91	6227	1	Open
Wasatch	Jun-91	6293	1	Open
Wasatch	Jun-91	6332	1	Open

WELL HISTORY:

- 4/1/91 – Spud well; 6/6/91– TD'd @ 6377'
- 6/13/91 – Perf gross Wasatch interval f/ 5013' – 6332'. Breakdown w/ 4000 gals 3% Kcl water.
- 6/16/91 – Pumped tob job in prod casing annulus, TOC @ surface.
- 11/12/91 – Frac Was interval w/ 352,000# sand & 30% CO2. Flowing @ 1400 MCFD after frac.
- 10/25/94 – Install siphon string
- 5/7/97 - Remove CT, Lower Tubing and Install PLE

REMARKS:

- Land Exploration/Operations - This well produced from the Wasatch formation. The lease is held by the NB Unit. OK to T&A. – Jason Rayburn
- Geology - Current production of 90 MCFD and 0.4 BCF of remaining reserves. Suggest to TA during drilling and completions operations of NBU 921-26D pad. Bring back online after completions operations of pad.
- Reservoir Engineering - Current production of 90 MCFD and 0.4 BCF of remaining reserves. Suggest to TA during drilling and completions operations of NBU 921-26D pad. Bring back online after completions operations of pad.
- Operations Engineering - Well produces 90 mcf and 0.4BCF of reserves. Incremental NPV 10 over PA is over \$400k. MB 12/21/2009

Recommended future action for disposition of well bore:

Temporarily abandon the wellbore during the drilling and completion operations of the NBU 921-26D pad wells (921-26C3CS, 921-26D3AS, & 921-26D3DS). Return to production as soon as possible once completions are done.

NBU 132 TEMPORARY ABANDONMENT PROCEDURE

GENERAL

- H2S MAY BE PRESENT. CHECK FOR H2S AND TAKE APPROPRIATE PRECAUTIONS.
- CEMENT QUANTITIES BELOW ASSUME NEAT CLASS G, YIELD 1.145 CUFT./SX. IF A DIFFERENT PRODUCT IS USED, WELLSITE PERSONNEL ARE RESPONSIBLE FOR CORRECTING QUANTITIES TO YIELD THE STATED SLURRY VOLUME. WHEN SQUEEZING, INCLUDE 10% EXCESS PER 1000' OF DEPTH.
- TREATED FRESH WATER WILL BE PLACED BETWEEN ALL PLUGS INSTEAD OF BRINE.
- ALL DISPLACEMENT FLUID SHALL CONTAIN CORROSION INHIBITOR AND BIOCIDES. PREMIX 5 GALLONS PER 100 BBLs FLUID.
- NOTIFY BLM 24 HOURS BEFORE MOVING ON LOCATION.


PROCEDURE

Note: An estimated 29 sx Class "G" cement needed for procedure

Note: Gyro has been run to 6200'

1. MIRU. KILL WELL AS NEEDED. ND WH, NU AND TEST BOPE.
2. PULL TBG & LD SAME. RU WIRELINE AND MAKE A GAUGE RING RUN TO CHECK FOR FILL.
3. **PLUG #1, ISOLATE WASATCH PERFORATIONS (5014' - 6332')**: RIH W/ 4 1/2" CBP. SET @ ~4964'. RELEASE CBP, PUH 10', BRK CIRC W/ FRESH WATER. PRESSURE TEST CASING TO 500 PSI. INFORM ENGINEERING IF IT DOESN'T TEST. DISPLACE A MINIMUM OF 6.53 CUFT CMT (~6 SX) ON TOP OF PLUG. PUH ABOVE TOC (~4914'). REVERSE CIRCULATE W/ TREATED FRESH WATER.
4. **PLUG #2, PROTECT WASATCH TOP (4760')**: PUH TO ~4860'. BRK CIRC W/ FRESH WATER. DISPLACE 26.10 CUFT. (~23 SX) AND BALANCE PLUG W/ TOC @ ~4660' (200' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED FRESH WATER.
5. LOWER WELLHEAD TO GROUND LEVEL TO ACCOMMODATE DRILLING OPS AND INSTALL MARKER PER BLM GUIDELINES.
6. RDMO. TURN OVER TO DRILLING OPERATIONS.

ALM 2/1/10



RECEIVED February 02, 2010

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UO1194ST
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 132
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.	9. API NUMBER: 43047319380000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6007 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0594 FNL 0850 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 26 Township: 09.0S Range: 21.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/20/2010	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input checked="" type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THE OPERATOR HAS COMPLETED THE TEMPORARILY ABANDON OPERATIONS ON THE SUBJECT WELL LOCATION. THE OPERATOR HAS TEMPORARILY ABANDONED THE WELL TO DRILL THE NBU 921-26D PAD WELLS WHICH CONSISTS OF THE NBU 921-26C3CS, NBU 921-26D3AS, AND NBU 921-26D3DS. PLEASE REFER TO THE ATTACHED TEMPORARILY ABANDON CHRONOLOGICAL WELL HISTORY.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY
 April 21, 2010

NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A		DATE 4/21/2010

US ROCKIES REGION
Operation Summary Report

Well: NBU 132		Spud Date:	
Project: UTAH-UINTAH		Site: NBU 132	Rig Name No: MILES 2/2
Event: ABANDONMENT		Start Date: 4/15/2010	End Date: 4/20/2010
Active Datum: RKB @0.00ft (above Mean Sea Level)		UWI: NBU 132	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
4/16/2010	7:00 - 7:30	0.50	ABAND	48		P		RDMO, MIRU
	7:30 - 7:30	0.00	ABAND	30				RD ON NBU 165, MOVE TO NBU 132, RU ON LOC, KILL WELL WITH 00 BBLS TMAC, ND WH, NU BOP'S, UNLAND TBG, SWIFN.
4/19/2010	7:00 - 7:30	0.50	ABAND	48		P		SCANNING TBG
	7:30 - 7:30	0.00	ABAND	45		P		CSG 400#, TBG 0#, RU PRS, POOH SCANNING TBG, RU CUTTERS, RIH GAUGE RING TO 5005', POOH LD GAUGE RING, PU 5 1/2' CBP, RIH TO 4964' SET CBP, POOH , PU BAILER, RUN IN HOLE (3 TRIPS) BAIL 6 SX CLASS G CEMENT ON TOP OF CBP. POOH LD BAILER, RD CUTTERS, PU TBG RIH WITH 127 JTS TBG TO 3982.45'. SWIFN
4/20/2010	7:00 - 7:30	0.50	ABAND	48		P		PUMP CEMENT
	7:30 - 7:30	0.00	ABAND	51		P		RIH 28 JTS TO 4857', RU PRO PETRO, ROLL HOLE BTMS UP, PRESSURE TEST CSG TO 500#,SET PLUG, 25 SX CLASS G CEMENT, 5 BBLS, 28.6 CF, Y 1.145, 4.9 GALW/SX, WT, 15.8#, DISPLACE WITH 1 BBL FRESH, 16.9 BBLS TMAC. RD PRO PETRO, POOH , LD TBG STRING, CAP WELL, RDMO TO NBU 259.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	FORM 9 5. LEASE DESIGNATION AND SERIAL NUMBER: UO1194ST
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 132
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.	9. API NUMBER: 43047319380000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6007 Ext
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0594 FNL 0850 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNW Section: 26 Township: 09.0S Range: 21.0E Meridian: S	9. FIELD and POOL or WILDCAT: NATURAL BUTTES COUNTY: UINTAH STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/26/2010	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

THIS PREVIOUSLY TEMPORARILY ABANDONED WELL HAS RETURNED TO PRODUCTION. THIS WELL RETURNED TO PRODUCTION ON 8/26/2010 AT 09:00 HRS.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 August 31, 2010

NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst
SIGNATURE N/A		DATE 8/30/2010